APPENDIX M (Cont'd) Bid Package – Tamarack Creek

ROUGE RIVER AOC HABITAT PROJECT: TAMARACK CREEK - STREAM AND WETLAND RESTORATION





SOUTHFIELD, MICHIGAN

GLRI EPA DESIGN AWARD NO. GL-00E02344 GLRI EPA IMPLEMENTATION AWARD NO. GL-00E02478 FOR BIDDING JANUARY 2021






PREPARED BY:




WITH:










NOT TO SCALE

DRAWING INDEX

- **COVER SHEET**
- **EXISTING CONDITIONS OVERVIEW**
- **EXISTING CONDITIONS ZONE A**
- **EXISTING CONDITIONS ZONE B**
- **EXISTING CONDITIONS ZONE C**
- **EXISTING CONDITIONS ZONE D**
- TREE INVENTORY
- SITE PREPARATION PLAN
- **DEMOLITION PLAN**
- PROPOSED PLAN OVERVIEW
- PROPOSED PLAN ZONE A
- PROPOSED PLAN ZONE B
- PROPOSED PLAN ZONE C
- PROPOSED PLAN ZONE D
- PROPOSED REVEGETATION PLAN OVERVIEW
- PROPOSED REVEGETATION PLAN ZONE A
- PROPOSED REVEGETATION PLAN ZONE B
- PROPOSED REVEGETATION PLAN ZONE C
- PROPOSED REVEGETATION PLAN ZONE D
- **REVEGETATION DETAILS (1/2)**
- **REVEGETATION DETAILS (2/2)**
- CROSS-SECTIONS (1/3)
- CROSS-SECTIONS (2/3)
- CROSS-SECTIONS (3/3)
- PROFILE (1/2)
- PROFILE (2/2)
- DETAILS (1/2)
- DETAILS (2/2)



— — PROPERTY LINEFEMA 100-YR FLOOD BOUNDARY

EXISTING WETLAND

EXISTING SITE CONDITIONS:

- 1. CONTRACTOR SHALL BECOME FAMILIAR WITH ALL EXISTING SITE CONDITIONS PRIOR TO STARTING WORK.
- 2. THE CONTRACTOR UNDERSTANDS AND ACKNOWLEDGES THAT THE PERFORMANCE OF THE WORK IS REQUIRED WITHIN THE ROUGE RIVER SYSTEM AND FLOODPLAIN AND THAT THE ROUGE RIVER WATER LEVEL FLUCTUATES.
- 3. THE CONTRACTOR UNDERSTANDS AND ACKNOWLEDGES THAT THEY HAVE TAKEN INTO ACCOUNT THE POTENTIAL FOR ANY WATER LEVEL CHANGES THAT MIGHT OCCUR IN COSTING, SCHEDULING, AND FEASIBILITY OF PERFORMING THE CONTRACT WORK UNDER THE PREVAILING ENVIRONMENTAL CONDITIONS. THEREFORE THE CONTRACTOR ACKNOWLEDGES THAT ANY FLUCTUATION IN WATER LEVELS, FLOODING, OR INUNDATION DURING/OVER THE COURSE OF THE PROJECT IS LIKELY AND DOES NOT CONSTITUTE A CHANGE IN CONDITIONS OR AN UNFORESEEN SITE CONDITION.
- 4. THE CONTRACTOR SHALL BE FULLY AWARE OF THE ROUGE RIVER HYDROLOGY AND CURRENT WEATHER CONDITIONS SO THAT WORK CAN BE SECURED AND PROTECTED AT ALL TIMES, SO THAT SAFE JOB SITE WORKING CONDITIONS ARE MAINTAINED, AND SO THAT SOIL EROSION IS CONTROLLED IN ACCORDANCE WITH ALL APPLICABLE PERMITS AND ENVIRONMENTAL LAWS.

SURVEY INFORMATION PROVIDED BY MIDWESTERN

SURVEY WAS CONDUCTED IN DECEMBER, 2018

PRIOR TO CONSTRUCTION AS NEEDED

ALL ELEVATIONS SHOWN ARE IN NAVD88 DATUM

CONTRACTOR TO CONFIRM EXISTING CONDITIONS

5. THE CONTRACTOR ACKNOWLEDGES THAT DELAYS IN THE START OF, OR COMPLETION OF. WORK DUE TO FLUCTUATIONS IN WATER LEVEL THROUGHOUT THE DURATION OF THE PROJECT SHALL NOT CONSTITUTE A CHANGE IN CONDITIONS NOR SHALL BE A BASIS FOR ANY EXTENSION OF TIME OR DAMAGES. IF THE CONTRACTOR SHALL BE UNAVOIDABLE DELAYED IN BEGINNING OR FULFILLING THIS CONTRACT BY REASONS OF CHANGING WATER LEVELS, STORMS, INUNDATION OR FLOODS THE CONTRACTOR SHALL HAVE NOT VALID CLAM FOR DAMAGES, BUT SHALL IN SUCH CASE BE ENTITLED TO AN EXTENSION OF TIME AS THE ENGINEER SHALL ADJUDGE TO BE JUST AND REASONABLE, PROVIDED THAT FORMAL CLAIM FOR AN EXTENSION OF TIME IS MADE IN WRITING BY THE CONTRACTOR WITHIN 14 DAYS OF THE ALLEGED DELAY.

6. THE ENGINEER RESERVES THE RIGHT TO SUSPEND WORK ACTIVITIES WHEN IT IS IN THE BEST INTEREST OF THE PROJECT TO DO SO DUE TO WEATHER, FLOW, OR WATER LEVEL CONDITIONS. THE DIRECTIVE TO SUSPEND WORK ACTIVITIES SHALL BE SUBMITTED TO THE CONTRACTOR, BY THE ENGINEER, IN WRITING. SUCH SUSPENSION SHALL NOT BE BASIS FOR CLAIM FOR ADDITIONAL COST BUT CAN BE BASIS FOR EXTENSION OF TIME.

- 7. THE CONTRACTOR SHALL RESEARCH AVAILABLE INFORMATION AND PERFORM ITS OWN INDEPENDENT INVESTIGATIONS AS NEEDED IN AN EFFORT TO FULLY UNDERSTAND ENVIRONMENTAL CONDITIONS ASSOCIATED WITH THE PROJECT SITE. THE CONTRACTOR SHALL UNDERSTAND THE SITE CONDITIONS THAT WILL AFFECT THE COST, SCHEDULE, OR PERFORMANCE OF WORK IN ADVANCE OF STARTING SUCH WORK.
- 8. TOPOGRAPHIC SURVEY INFORMATION PROVIDED BY MIDWESTERN CONSULTING, INC SURVEY CONDUCTED IN DECEMBER, 2018.
- 9. ALL ELEVATIONS SHOWN ARE IN NAVD88 DATUM.

10. CONTRACTOR TO CONFIRM EXISTING CONDITIONS PRIOR TO CONSTRUCTION, AND REPORT ANY DISCREPANCIES TO PROJECT TEAM PRIOR TO COMMENCING WORK ACTIVITIES.

- 11. SEDIMENT SAMPLE LABORATORY DATA IS AVAILABLE UPON REQUEST
- 12. FULL TREE INVENTORY IS AVAILABLE UPON REQUEST
- 13. BENCHMARK INFORMATION SHOWN BELOW.

BENCHMARK #1

TOP OF CONCRETE HEADWALL OVER 72" CULVERT LOCATED +/-510' SOUTH OF THE C/L 10 MILE ROAD; +/- 55' SOUTH OF SOUTHEAST CORNER OF BUILDING; +/- 35' EAST OF TREE (TAG #1022, 15" BOX ELDER).

ELEVATION = 660.60 (NAVD 88 DATUM)

BENCHMARK #2

TOP OF SPIKE SET IN SOUTHEAST FACE OF TREE (TAG #1278, 18" RED OAK); +/-47' NORTHEAST OF C.P. #3096; +/-31' WEST OF THE CENTERLINE OF TAMARACK CREEK; +/-179' SOUTH-SOUTHWEST OF C.P. #11.

ELEVATION = 660.92 (NAVD 88 DATUM)

GENERAL NOTES:

1. UNDERGROUND UTILITIES: FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 53, 1974, THE CONTRACTOR SHALL DIAL 1-800-482-7171 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.

2. SURVEY DATA PRESENTED IN THESE DRAWINGS WAS PROVIDED BY:

MIDWESTERN CONSULTING 3815 PLAZA DRIVE

CONSULTING, INC.

ANN ARBOR, MICHIGAN 48108

ANN ARBOR, MICHIGAN 48108 (734) 995-0200 (PH)

- 3. THE SOIL LOG INFORMATION (ATTACHED TO BID SPECIFICATIONS) REPRESENTS POINT INFORMATION. PRESENTATION OF THIS INFORMATION IN NO WAY INFERS THAT SUBSURFACE CONDITIONS ARE THE SAME OTHER THAN THE EXACT LOCATION OF THE BORINGS.
- 4. STORAGE OF EQUIPMENT AND CONSTRUCTION MATERIALS SHALL BE RESTRICTED TO DESIGNATED STAGING AREAS AS INDICATED ON THE PLANS, UNLESS OTHERWISE APPROVED BY ENGINEER.
- 5. ALL UTILITIES, CULVERTS AND BENCHMARKS SHALL BE PRESERVED DURING CONSTRUCTION ACTIVITIES UNLESS OTHERWISE SHOWN ON THE DRAWINGS. CONTRACTOR TO REPLACE DAMAGED UTILITIES, CULVERTS OR BENCHMARKS AT OWN EXPENSE.
 6. ALL CONSTRUCTION ACTIVITIES SHALL BE LIMITED TO 'LIMIT OF DISTURBANCE' LINE. WORK BEYOND THESE LIMITS SHALL BE AS DIRECTED BY ENGINEER.
- 7. TRANSPORTATION OF EQUIPMENT AND MATERIALS TO/FROM THE SITE ON STATE HIGHWAYS AND TRUNK LINES SHALL CONFORM TO ALL LOCAL AND STATE TRAFFIC LAWS. CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS PERTAINING TO DELIVERY OF EQUIPMENT AND MATERIALS TO/FROM THE SITE. COSTS OF OBTAINING NECESSARY PERMITS IS INCIDENTAL TO THE WORK.

 8. ALL WORK SHALL BE COMPLETED BETWEEN THE HOURS OF 7:00AM AND 6:00PM. ALL WORK SHALL BE COMPLETED MONDAY THROUGH SATURDAY.
- 9. CONSTRUCTION ACCESS TO THE SITES FOR ALL ACTIVITIES WILL BE FROM AUDREY LANE (OFF OF 10 MILE) AS INDICATED ON THE SITE ACCESS PLAN. NO OTHER ACCESS IS ALLOWED WITHOUT WRITTEN PERMISSION FROM THE OWNER.
- 10. ALL MATERIALS REMOVED, EXCEPT WHERE OTHERWISE INDICATED ON THE PLANS, SHALL BE LEGALLY DISPOSED OF OFF SITE.
- 11. ALL EXCESS SOIL AND FILL GENERATED DURING REQUIRED EXCAVATION AS SHOWN ON DRAWINGS SHALL BE LEGALLY DISPOSED OF OFF-SITE.

 12. THE CONTRACTOR SHALL OBTAIN PERMITS AS REQUIRED FOR THE PROJECT, INCLUDING THE SOIL EROSION AND SEDIMENT CONTROL PERMIT FROM
- 12. THE CONTRACTOR SHALL OBTAIN PERMITS AS REQUIRED FOR THE PROJECT, INCLUDING THE SOIL EROSION AND SEDIMENT CONTROL PERMIT FROM THE CITY OF SOUTHFIELD.
- 13. THE EGLE/USACE PERMIT HAS BEEN ACQUIRED. ALL WORK SHALL BE DONE TO MEET THE REQUIREMENTS OF EGLE AND/OR USACE PERMITS ISSUED FOR THIS PROJECT. A COPY OF THE PERMIT IS INCLUDED IN THE CONTRACT DOCUMENTS.

3 WORKING DAYS BEFORE YOU DIG CALL MISS DIG 1-800-482-7171







ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT


SOUTHFIELD, MICHIGAN

EOR BIDDING 01-2021
EGLE/USACE JOINT PERMIT APP. 06-2020

180611-0300
ECT PROJECT NUMBER


AB MB

EXISTING
CONDITIONS OVERVIEW






BASE SURVEY CONDUCTED BY MIDWESTERN CONSULTING IN DECEMBER 2018



LEGEND EXIST. CONTOUR EXIST. UTILITY POLE EXIST. OVERHEAD UTILITY LINE EXIST. LIGHT POLE EXIST. TELEPHONE LINE EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET **END SECTION** CULVERT **FENCE** SINGLE TREE SECTION CORNER CONTROL PT. SOIL BORING LOCATION EXIST. BUILDING EXIST. STREAM CENTERLINE EXIST.PROPERTY LINE FEMA 100-YR FLOOD BOUNDARY EXIST. WETLAND

INDEX MAP



- NOTES:

 1. SURVEY INFORMATION PROVIDED BY MIDWESTERN CONSULTING, INC.
- 2. SURVEY WAS CONDUCTED IN DECEMBER, 2018
- 3. ALL ELEVATIONS SHOWN ARE IN NAVD88 DATUM 4. CONTRACTOR TO CONFIRM EXISTING CONDITIONS
- PRIOR TO CONSTRUCTION AS NEEDED
- 5. SEE EXISTING CONDITIONS NOTES ON SHEET 2

BENCHMARK #1

TOP OF CONCRETE HEADWALL OVER 72" CULVERT LOCATED +/-510' SOUTH OF THE C/L 10 MILE ROAD; +/- 55' SOUTH OF SOUTHEAST CORNER OF BUILDING; +/- 35' EAST OF TREE (TAG #1022, 15" BOX ELDER).

3 WORKING DAYS

BEFORE YOU DIG

CALL MISS DIG

1-800-482-7171

ELEVATION = 660.60 (NAVD 88 DATUM)

TOP OF SPIKE SET IN SOUTHEAST FACE OF TREE (TAG #1278, 18" RED OAK); +/-47' NORTHEAST OF C.P. #3096; +/-31' WEST OF THE CENTERLINE OF TAMARACK CREEK; +/-179'

ELEVATION = 660.92 (NAVD 88 DATUM)

Ann Arbor, Michigan 48105

734.769.3004

734.769.3164 fax





ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**

EGLE/USACE JOINT PERMIT APP.

180611-0300 ECT PROJECT NUMBER AB MB


DESIGNED BY CHECKED BY


AT DRAWN BY - **JO** APPROVED BY


> **EXISTING CONDITIONS** -**ZONE A**

SCALE: 1" = 40' @ 22" x 34" SHEET NUMBER









EXIST. CONTOUR EXIST. UTILITY POLE EXIST. OVERHEAD UTILITY LINE EXIST. LIGHT POLE EXIST. TELEPHONE LINE EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET **END SECTION** CULVERT **FENCE** SINGLE TREE

CONTROL PT. FEMA 100-YR FLOOD BOUNDARY


> EXIST. BUILDING EXIST. STREAM CENTERLINE

SECTION CORNER

EXIST. PROPERTY LINE

EXIST. WETLAND

INDEX MAP



- NOTES:

 1. SURVEY INFORMATION PROVIDED BY MIDWESTERN CONSULTING, INC.
- 2. SURVEY WAS CONDUCTED IN DECEMBER, 2018
- ALL ELEVATIONS SHOWN ARE IN NAVD88 DATUM
- 4. CONTRACTOR TO CONFIRM EXISTING CONDITIONS PRIOR TO CONSTRUCTION AS NEEDED
- 5. SEE EXISTING CONDITIONS NOTES ON SHEET 2

TOP OF CONCRETE HEADWALL OVER 72" CULVERT LOCATED +/-510' SOUTH OF THE C/L 10 MILE ROAD; +/- 55' SOUTH OF SOUTHEAST CORNER OF BUILDING; +/- 35' EAST OF TREE (TAG #1022, 15" BOX ELDER).

ELEVATION = 660.60 (NAVD 88 DATUM)

TOP OF SPIKE SET IN SOUTHEAST FACE OF TREE (TAG #1278, 18" RED OAK); +/-47' NORTHEAST OF C.P. #3096; +/-31' WEST OF THE CENTERLINE OF TAMARACK CREEK; +/-179' SOUTH-SOUTHWEST OF C.P. #11.

ELEVATION = 660.92 (NAVD 88 DATUM)

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND **RESTORATION PROJECT**

Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax

Working together, restoring the river

SOUTHFIELD, **MICHIGAN**

FOR BIDDING EGLE/USACE JOINT PERMIT APP. 06-2020

EXISTING CONDITIONS -**ZONE D**



TREES TO BE REMOVED

TAG#	DBH	COMMON NAME	GENUS/SPECIES	LANDMARK
257 486	7 7	Box Elder Black Walnut	Acer negundo Juglans nigra	
487	7	American Elm	Ulmus americana	
488 490	12 6	Box Elder Black Willow	Acer negundo Salix nigra	
684	14	Black Walnut	Juglans nigra	
685	10	Black Walnut	Juglans nigra	
686 687	15 10	Black Walnut Black Walnut	Juglans nigra Juglans nigra	
688	12	Black Walnut	Juglans nigra	
689	8	Black Walnut	Juglans nigra	
690 691	9	White Mulberry White Mulberry	Morus alba Morus alba	
692	23	White Pine	Pinus strobus	X
693	11	American Elm	Ulmus americana	
694 695	9 27	Black Cherry White Pine	Prunus serotina Pinus strobus	X
696	13	White Pine	Pinus strobus	, , , , , , , , , , , , , , , , , , ,
697	11	White Pine	Pinus strobus	V
698 700	29 12	Linden Black Walnut	Tilia americana Juglans nigra	X
701	16	Black Walnut	Juglans nigra	
702	9	Black Walnut	Juglans nigra	
703 704	6	White Ash American Elm	Fraxinus americana Ulmus americana	
705	14	Black Willow	Salix nigra	
706	18	Black Willow	Salix nigra	
707 736	13 19	Black Willow Black Walnut	Salix nigra Juglans nigra	
737	20	Black Walnut	Jugians nigra Jugians nigra	X
745	18	Box Elder	Acer negundo	
753 754	10 10	Black Maple Black Maple	Acer nigrum Acer nigrum	
75 4 755	8	American Elm	Ulmus americana	
756	25	Silver Maple	Acer saccharinum	X
757 758	26 10	Silver Maple Dogwood	Acer saccharinum Cornus florida	X
759	39	Cottonwood	Populus deltoides	X
760	11	Silver Maple	Acer saccharinum	
775 776	7 8	Black Maple Black Maple	Acer nigrum Acer nigrum	
777	9	Black Walnut	Juglans nigra	
781	7	White Ash	Fraxinus americana	
787 788	7 8	American Elm Black Walnut	Ulmus americana	
700 789	10	Black Wallfut Black Maple	Juglans nigra Acer nigrum	
790	13	Black Maple	Acer nigrum	
791 702	8	Black Maple	Acer nigrum	
792 807	35 7	Cottonwood Linden	Populus deltoides Tilia americana	X
808	8	American Elm	Ulmus americana	
809	7	American Elm	Ulmus americana	
818 821	11 33	Linden Black Maple	Tilia americana Acer nigrum	X
865	11	Black Maple	Acer nigrum	
866	10	Red Oak	Quercus rubra	
867 868	17 14	Red Oak Red Oak	Quercus rubra Quercus rubra	
869	10	Sugar Maple	Acer saccharum	
870	25	Cottonwood	Populus deltoides	Х
871 872	7 18	Hop-Hornbeam White Oak	Ostrya virginia Quercus alba	X
873	6	Hop-Hornbeam	Ostrya virginia	
874	6	Northern Hackberry	Celtis occidentalis	
875 877	13 10	Black Maple Black Maple	Acer nigrum Acer nigrum	
904	21	Black Cherry	Prunus serotina	X
905	15	Red Oak	Quercus rubra	
906 1036	9	White Pine Silver Maple	Pinus strobus Acer saccharinum	
1069	22	Black Walnut	Juglans nigra	X
1070	35	Black Willow	Salix nigra	Х
1071 1072	8 10	Box Elder Box Elder	Acer negundo Acer negundo	
1072	28	Black Willow	Salix nigra	X
1074	24	Black Willow	Salix nigra	X
1075 1076	17 8	Black Willow Box Elder	Salix nigra Acer negundo	
1077	13	Black Willow	Salix nigra	
1079	10	Black Walnut	Juglans nigra	
1080 1081	12 12	Black Willow Black Walnut	Salix nigra Juglans nigra	
1082	9	Box Elder	Acer negundo	
1083	12	Black Willow	Salix nigra	
1084 1086	9 15	Black Willow Black Willow	Salix nigra Salix nigra	
1087	26	Black Willow	Salix nigra Salix nigra	X
1088	17	Black Willow	Salix nigra	
1089 1090	11 10	Black Willow	Salix nigra	
1090 1091	10	Black Willow Black Willow	Salix nigra Salix nigra	
1092	14	Black Willow	Salix nigra	
1093	15	Black Willow	Salix nigra	
1094 1095	9 20	American Elm American Elm	Ulmus americana Ulmus americana	X
	16	Black Willow	Salix nigra	
1096				
1096 1097 1098	11	Wild Plum Silver Maple	Prunus americana Acer saccharinum	

AG#	DBH 11	COMMON NAME American Elm	GENUS/SPECIES	LANDMAR
1100	17		Ulmus americana	
1102 1103	18	Black Willow Black Willow	Salix nigra Salix nigra	
1104	11	White Ash	Fraxinus americana	
1105	16	Sugar Maple	Acer saccharum	
1106	35	Cottonwood	Populus deltoides	Х
1109	15	Black Willow	Salix nigra	
1110	10	Sugar Maple	Acer saccharum	
1111	12	Sugar Maple	Acer saccharum	
1112	10	Sugar Maple	Acer saccharum	
1113	9	Sugar Maple	Acer saccharum	
1114	12	Sugar Maple	Acer saccharum	
1115 1116	8	Sugar Maple	Acer saccharum Acer saccharum	
1117	13	Sugar Maple Sugar Maple	Acer saccharum Acer saccharum	
1118	9	Sugar Maple Sugar Maple	Acer saccharum	
1119	26	Black Willow	Salix nigra	X
1120	19	Black Willow	Salix nigra	
1121	11	Sugar Maple	Acer saccharum	
1122	14	Sugar Maple	Acer saccharum	
1123	9	Sugar Maple	Acer saccharum	
1124	9	Sugar Maple	Acer saccharum	
1125	10	Sugar Maple	Acer saccharum	
1126	29	Black Willow	Salix nigra	Х
1127	24	Black Willow	Salix nigra	Х
1128	9	American Elm	Ulmus americana	
1129	8	Sugar Maple	Acer saccharum	
1130	8	American Elm	Ulmus americana	
1131	11	Sugar Maple	Acer saccharum	
1132	8	American Elm	Ulmus americana	
1133	8	Sugar Maple	Acer saccharum	
1134	16	Sugar Maple	Acer saccharum	
1135	8 13	Sugar Maple Red Elm	Acer saccharum Ulmus rubra	
1136 1137	10	Linden	Tilia americana	
1138	19	Cottonwood		
1130	8	Linden	Populus deltoides Tilia americana	
1153	15	Black Willow	Salix nigra	
1154	16	Black Willow	Salix nigra	
1155	20	Black Willow	Salix nigra	
1156	24	Black Willow	Salix nigra	Х
1157	23	Black Willow	Salix nigra	
1158	8	American Elm	Ulmus americana	
1159	15	Box Elder	Acer negundo	
1160	18	Box Elder	Acer negundo	
1162	9	Black Walnut	Juglans nigra	
1167	14	Black Willow	Salix nigra	
1168	8	Silver Maple	Acer saccharinum	
1169	9	American Elm	Ulmus americana	
1172	17	Box Elder	Acer negundo	
1173	13	Black Willow	Salix nigra	
1174	11	Black Willow	Salix nigra	
1175 1176	13 14	Black Willow Black Willow	Salix nigra	
1176 1178	11	American Elm	Salix nigra Ulmus americana	
1178 1179	10	Black Maple	Acer nigrum	_
1180	10	American Elm	Ulmus americana	
1181	11	American Elm	Ulmus americana	
1182	18	American Elm	Ulmus americana	Х
1183	10	American Elm	Ulmus americana	
1184	9	Black Walnut	Juglans nigra	
1185	20	Cottonwood	Populus deltoides	
1186	11	American Elm	Ulmus americana	
1188	21	Cottonwood	Populus deltoides	
1189	8	Black Maple	Acer nigrum	
1190	15	American Elm	Ulmus americana	
1191	8	American Elm	Ulmus americana	
1192	14	Black Maple	Acer nigrum	
1202	23 13	Cottonwood	Populus deltoides	
1323 1324	13	Red Oak American Elm	Quercus rubra Ulmus americana	
1324 1325	14	Sugar Maple	Acer saccharum	
1325 1326	14	American Elm	Ulmus americana	
1320	25	American Elm	Ulmus americana	X
1328	17	Red Oak	Quercus rubra	
1329	26	Silver Maple	Acer saccharinum	X
1330	8	Black Maple	Acer nigrum	
1331	10	Black Maple	Acer nigrum	
יטטו				A CONTRACTOR OF THE CONTRACTOR

NOTE: THE LIST ABOVE INCLUDES ONLY TREES TO BE REMOVED.
A FULL TREE INVENTORY IS AVAILABLE UPON REQUEST.

EX. WETLAND 1 EXISTING ROAD — EX: WETLAND 2 WETLAND 3 TREE REMOVAL AND CLEARING LIMITS PLAN

INDIANA BAT: ANY TREES 3 INCHES DBH OR LARGER IS TO BE CONSIDERED BAT HABITAT. NO TREES OF THIS SIZE ARE TO BE CUT BETWEEN APRIL 1 AND SEPTEMBER 30 IN ANY YEAR TO AVOID TAKE OF INDIANA BAT (MYOTIS SODALIS), A FEDERALLY LISTED ENDANGERED SPECIES, UNLESS THE TREE IS CERTIFIED BY A BIOLOGIST NOT TO BE APPLICABLE HABITAT.

LEGEND

EXIST. CONTOUR
PROPERTY LINE

EXISTING WETLAND

CLEARING LIMITS







ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN


FOR BIDDING 01-2021
EGLE/USACE JOINT PERMIT APP. 06-2020

ECT PROJECT NUMBER


AB MB

AT JO
DRAWN BY APPROVED

TREE INVENTORY







TEMPORARY CONSTRUCTION SIGN

WHITE BACKGROUND Tamarack Creek - Stream and Wetland Restoration Rouge River AOC Habitat Design **Alliance of Rouge Communities** BLACK This project is funded by the U.S. Environmental Protection Agency Great Lakes National Program Office. A \$583,220 Great Lakes Restoration Initiative Grant (Grant No. 00E02344) funded project design; a portion of a \$3,308,139 Great Lakes Restoration Initiative Grant (Grant No. 00E02478) funds project implementation. Both grants were received by Alliance of Rouge Communities. Great Lakes RESTORATION Engineer: ECT Environmenta Contractor: (Insert Logo Here)

> SIGN DIMENSIONS: 1200 mm x 2400 mm x 19 mm (approx. 4' x 8' x 3/4") PLYWOOD PANEL (APA RATED A-B GRADE-EXTERIOR)

> > SIGN LOCATION TO BE DETERMINED IN FIELD WITH OWNER PRIOR TO COMSTRUCTION

SOIL EROSION CONTROL NOTES:

IN ACCORDANCE WITH RULE 1709 PROMULGATED UNDER THE AUTHORITY OF PART 91 SOIL EROSION AND SEDIMENT CONTROL, OF THE NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION ACT, 1994 PA 451, AS AMENDED, AND IN ADDITION TO THE INFORMATION IN THE PROJECT PLANS AND SPECIFICATIONS, THE FOLLOWING GENERAL CONDITIONS APPLY TO THE EARTH CHANGE AUTHORIZED BY THIS DOCUMENT.

. PROPOSED SECTIONS OF CHANNEL SHOULD NOT BE CONNECTED TO EXISTING CHANNEL UNTIL ALL PROPOSED SECTIONS ARE COMPLETE. CONNECTION OF PROPOSED SECTIONS TO EXISTING SECTIONS SHOULD BE DONE FROM DOWNSTREAM TO UPSTREAM WHILE PLUGGING EXISTING CHANNEL.

2. CONSTRUCT AND COMPLETE THE EARTH CHANGE IN ACCORDANCE WITH THE SOIL EROSION AND SEDIMENT CONTROL PERMIT AND IN A MANNER THAT LIMITS THE EXPOSED

AREA OF DISTURBED LAND FOR THE SHORTEST PERIOD OF TIME 3. TEMPORARY OR PERMANENT CONTROL MEASURES SHALL BE INSTALLED TO CONVEY 4. REMOVE SEDIMENT CAUSED BY ACCELERATED SOIL EROSION FROM RUNOFF WATER

BEFORE IT LEAVES THE SITE OF THE EARTH CHANGE 5. INSTALL TEMPORARY SOIL EROSION AND SEDIMENTATION MEASURES BEFORE OR UPON COMMENCEMENT OF THE EARTH CHANGE ACTIVITY AND MAINTAIN THE MEASURES ON A DAILY BASIS. REMOVE TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES AFTER PERMANENT SOIL EROSION MEASURES ARE IN PLACE AND THE AREA IS STABILIZED. ("STABILIZED" MEANS THE ESTABLISHMENT OF VEGETATION OR THE PROPER PLACEMENT, GRADING OR COVERING OF SOIL TO ENSURE ITS RESISTANCE TO SOIL

EROSION, SLIDING, OR OTHER EARTH MOVEMENT.)

CONTRACTOR IS RESPONSIBLE FOR MAINTAINING SITE DRAINAGE.

7. CONTRACTOR IS RESPONSIBLE TO PROTECT ADJACENT WATER COURSES FROM THE DISCHARGE OF SEDIMENT DURING CONSTRUCTION.

8. INSTALL PERMANENT EROSION CONTROL MEASURES WITHIN 5 DAYS OF COMPLETING FINAL GRADING OR MAINTAIN TEMPORARY MEASURES UNTIL PERMANENT MEASURES ARE INSTALLED.

9. SILT FENCE TO BE INSTALLED AROUND OFF-SITE STOCKPILE AREAS. 10. APPLY TEMPORARY EROSION CONTROL ON OVER EXPOSED SOILS DURING WET WEATHER AND WHEN SITE IS INACTIVE FOR MORE THAN 24 HOURS. 11. DO NOT CONSTRUCT DURING HIGH FLOW OR WET WEATHER.

12. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING LANDSCAPING DURING THE WARRANTY PERIOD.

13. PROTECT ALL DRAIN INLETS WITH SEDIMENT FILTERS.

14. EXISTING LOW AREAS TO BE USED FOR STORMWATER DETENTION AND SETTLING DURING CONSTRUCTION.

CLEARING AND GRUBBING NOTES

1. REVIEW CLEARING LIMITS AND TREE REMOVALS WITH PROJECT ENGINEER PRIOR TO BEGINNING WORK.

2. ALL SILT FENCE AND PROTECTIVE FENCE SHALL BE INSTALLED PRIOR TO CLEARING OPERATIONS. ALL FENCING SHALL BE MAINTAINED THROUGHOUT DURATION OF PROJECT. FENCING SHALL BE REMOVED ONLY UPON APPROVAL BY ENGINEER.

3. ALL PLANT MATERIAL NOT MARKED FOR REMOVAL SHALL BE DISTURBED AS LITTLE AS POSSIBLE DURING THE CLEARING AND CONSTRUCTION OPERATIONS. NO EXCAVATION SHALL BE DONE WITHIN THE DRIP LINE (LIMIT OF OVERHANGING BRANCHES) OF TREES TO BE SAVED, UNLESS SPECIFICALLY APPROVED BY THE ENGINEER. THE LOWER BRANCHES OF ALL TREES TO REMAIN SHALL NOT BE REMOVED, OR DAMAGED BY CONSTRUCTION EQUIPMENT. AVOID COMPACTION OF ROOTS.

4. HYDRO AXE AND/OR SIMILAR CLEARING EQUIPMENT SHALL NOT BE PERMITTED ON SITE.

STAGING/ ACCESS NOTES:

1. EQUIPMENT ACCESS AND STAGING AND MATERIALS STORAGE CAN OCCUR WITHIN THE LIMITS OF DISTURBANCE IN ADDITION TO DESIGNATED STAGING AREAS. NO ADDITIONAL VEGETATION CLEARING FOR ACESS OR STAGING IS PERMITTED WITHOUT APPROVAL OF THE ENGINEER AND OWNER.

2. NO MATERIAL STORAGE OR EQUIPMENT STAGING IS PERMITTED ON ANY PORTION OF 10 MILE ROAD INCLUDING AREAS CLOSED TO TRAFFIC.

3. CONTRACTOR SHALL PROVIDE ADEQUATE PROTECTION OVER EXISTING ASPHALT ON AUDREY LANE TO PREVENT PHYSICAL DAMAGE OR CHEMICAL DAMAGE FROM LEAKING PETROLEUM PRDUCTS. REPAIR OF DAMAGED ROAD SHALL BE AT CONTRACTOR'S EXPENSE UNLESS SPECIFICALLY ACCOUNTED FOR UNDER CONTRACTOR'S SITE RESTORATION LINE ITEM.

15. INSTALL TEMPORARY INLET FILTERS AT ALL ADJACENT AND DOWN-GRADIENT STORM WATER INLETS, CATCH BASINS AND MANHOLES THAT MAY BE IMPACTED. CATCH BASIN INLET FILTERS SHALL BE MAINTAINED CLEAN AT ALL TIMES THROUGHOUT THE CONSTRUCTION PERIOD. IF A FILTER HAS HOLES OR IS INUNDATED WITH SEDIMENT THE FILTER WILL REQUIRE REPLACEMENT

16. INSTALL AN ANTI-TRACKING PAD AT THE SITE ENTRY AND EXIT(S). THE ANTI-TRACKING PAD SHOULD BE CONSTRUCTED OF GEOTEXTILE FABRIC WITH LIMESTONE OVER IT

17. SILT FENCE AND/OR TURBIDITY BARRIER SHALL BE MAINTAINED AT ALL TIMES THROUGHOUT THE CONSTRUCTION PERIOD. IF REPAIR OR REPLACEMENT IS NECESSARY, IT SHALL BE PERFORMED ACCORDING TO THE MANUFACTURER'S CONTRACTOR SHALL REMOVE, REPLACE IF IT FAILS. ADDITIONALLY, THE CONTRACTOR SHALL REINSTALL ANY PORTION OF THE FENCING/ BARRIER DAMAGED BY

18. PLACE STOCKPILES AND OTHER SPOIL PILES AWAY FROM THE DRAINAGE SYSTEM TO MINIMIZE SEDIMENT TRANSPORT. IF THE STOCKPILE AND/OR SPOIL PILE MUST REMAIN ON-SITE OVERNIGHT, OR IF THE WEATHER CONDITIONS INDICATE THE CHANCE FOR PRECIPITATION, A.) COVER THE PILE WITH WATER REPELLENT MATERIAL TO PREVENT EROSION AND/OR B.) INSTALL SILT FENCING AROUND THE BASE OF THE PILE TO PREVENT TRANSPORT OF SEDIMENT TO THE STORM WATER SYSTEM, OR APPLY OTHER CONTROL METHODS APPROPRIATE TO THE SITE. CONTROL MEASURES TO GUARD AGAINST WIND EROSION MUST ALSO BE EMPLOYED, SUCH AS WETTING OR COVERING THE STOCKPILES. KEEP AS FEW STOCKPILES AS POSSIBLE DURING THE COURSE OF THE PROJECT.

19. THROUGHOUT THE CONSTRUCTION PERIOD, ALL MUD/SILT TRACKED ONTO EXISTING ROADS FROM THE SITE DUE TO CONSTRUCTION SHALL BE IMMEDIATELY REMOVED BY THE CONTRACTOR.

20. SEEDING OR OTHER STABILIZATION SHALL BE REQUIRED IMMEDIATELY TO AREAS WHICH HAVE BEEN DAMAGED BY RUNOFF.

21. THE CONTRACTOR SHALL MAINTAIN DUST CONTROL ON THE SITE THROUGHOUT THE DURATION OF THE CONSTRUCTION PROCESS

22. SILT CURTAINS SHALL BE INSTALLED DOWNSTREAM OF HABITAT STRUCTURE CONSTRUCTION IN EXISTING STREAM

MISCELLANEOUS NOTES

- CONSTRUCTION MUST BE UNDERTAKEN AND COMPLETED DURING THE DRY PERIOD OF THE WETLAND. IF THE AREA DOES NOT DRY OUT, THE CONSTRUCTION SHALL BE DONE ON EQUIPMENT MATS TO
- PREVENT COMPACTION OF THE SOIL. 2. DURING REMOVAL OR REPAIR OR REPAIR OF EXISTING STRUCTURES, EVERY PRECAUTION SHALL BE TAKEN TO PREVENT DEBRIS FROM ENTERING ANY WATERCOURSE. ANY DEBRIS REACHING THE WATERCOURSE DURING THE REMOVAL AND/OR RECONSTRUCTION OF THE STRUCTURE SHALL BE IMMEDIATELY RETRIEVED FROM THE WATER. ALL MATERIAL SHALL BE DISPOSED OF IN AN
- ACCEPTABLE MANNER CONSISTENT WITH LOCAL, STATE, AND FEDERAL REGULATIONS. NO WORK SHALL BE DONE IN THE STREAM DURING PERIODS OF ABOVE-NORMAL FLOWS EXCEPT AS NECESSARY TO PREVENT EROSION.
- IF THE PROJECT, OR ANY PORTION OF THE PROJECT, IS STOPPED AND LIES INCOMPLETE FOR ANY LENGTH OF TIME (OTHER THAN THAT ENCOUNTERED IN A NORMAL WORK WEEK) EVERY PRECAUTION SHALL BE TAKEN TO PROTECT THE INCOMPLETE WORK FROM EROSION, INCLUDING THE PLACEMENT OF TEMPORARY GRAVEL BAG RIPRAP, TEMPORARY SEED AND MULCH, OR OTHER ACCEPTABLE TEMPORARY PROTECTION.
- PRIOR TO THE INITIATION OF ANY PERMITTED CONSTRUCTION ACTIVITIES, A SEDIMENTATION BARRIER SHALL BE CONSTRUCTED IMMEDIATELY DOWN GRADIENT OF THE CONSTRUCTION SITE. SEDIMENTATION BARRIERS SHALL BE SPECIFICALLY DESIGNED TO HANDLE THE SEDIMENT TYPE, LOAD, WATER DEPTH, AND FLOW CONDITIONS OF EACH CONSTRUCTION SITE THROUGHOUT THE ANTICIPATED TIME OF CONSTRUCTION AND UNSTABLE SITE CONDITIONS. THE SEDIMENTATION BARRIER SHALL BE MAINTAINED IN GOOD WORKING ORDER THROUGHOUT THE DURATION OF THE PROJECT. UPON PROJECT COMPLETION, THE ACCUMULATED MATERIALS SHALL BE REMOVED AND DISPOSED OF AT AN UPLAND (NON-WETLAND, NON-FLOODPLAIN) SITE AND STABILIZED WITH SEED AND MULCH. THE SEDIMENTATION BARRIER SHALL THEN BE REMOVED IN ITS ENTIRETY AND THE AREA RESTORED TO ITS ORIGINAL CONFIGURATION AND COVER.
- NO IN-STREAM WORK MAY OCCUR BETWEEN APRIL 15 AND JUNE 15 OF ANY CALENDAR YEAR THAT THIS PERMIT IS ACTIVE WITHOUT THE USE OF SILT CURTAINS TO SEGREGATE DEFINED WORK ZONES, WITH PROGRESSION OF WORK WITHIN ONE ZONE AT A TIME. IF SUCH WORK OCCURS THE PERMITTEE SHALL CONTACT EGLE 48 HOURS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES AND SUBMIT A PLAN DRAWING INDICATING SILT CURTAIN LAYOUT AND THE SEGREGATION OF WORK



734.769.3164 fax





ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**

3 WORKING DAYS BEFORE YOU DIG CALL MISS DIG 1-800-482-7171


FOR BIDDING 01-2021 EGLE/USACE JOINT PERMIT APP.

ECT PROJECT NUMBER

SITE **PREPARATION** PLAN

SCALE: 1" = 120' @ 22" x 34"





EXIST. CONTOUR EXIST. BUILDING EXIST. STREAM CENTERLINE EXIST. PROPERTY LINE EXIST. FENCE

PR. TREE REMOVAL (FOR LIST OF TREES TO BE REMOVED, SEE SHEET 7)

1 REMOVE CULVERT

1. REMOVE 16 LF OF EXISTING CULVERT

1. REMOVE 800 LF OF EXISTING FENCE AS NECESSARY FOR GRADING

1. 3 CMP CULVERTS 70 LF TO BE REMOVED INCLUDING BEDDING MATERIALS

IF PRESENT

2. 450 TONS OF CONCRETE RUBBLE

2000 CYDS FILL


4 REMOVE DRAIN TILE AS NEEDED

DRAIN TILE TO BE FIELD LOCATED AND REMOVED ONLY TO THE EXTENT AS NEEDED FOR PROPOSED EXCAVATION AND GRADING

 $\overline{5}$ REMOVE BRIDGE ABUTMENTS

1. 50 TONS REINFORCED CONCRETE ABUTMENTS AND FOOTINGS (~2 ton/cy)

INDEX MAP



NOTE: NO DEMOLITION NEEDED OUTSIDE OF THESE LIMITS, WITH THE EXCEPTION OF SOME TREE AND BRUSH CLEARING FOR THE ACCESS ROUTE. FOR TREE REMOVAL LIST, SEE

SITE CLEARING NOTES:

1. TOTAL SITE CLEARING AREA: 8.0 ACRES

SCHEDULING NOTES:

1. DUE TO FISH SPAWNING AND MIGRATION, NO IN-STREAM WORK SHALL OCCUR BETWEEN MARCH 15 AND JUNE 15.

TREE REMOVAL NOTES

1. TREES AS DESIGNATED ON THE LIST ON SHEET 7 TO BE REMOVED AS PART OF THIS PROJECT.

2. ALL TREES TO BE REMOVED AND ALL CLEARING TO BE FIELD VERIFIED BY ENGINEER PRIOR TO WORK ACTIVITIES.

3. SOME TREES MAY BE SALVAGED FOR USE IN HABITAT STRUCTURES AS SHOWN ON SHEET 24. TREES TO BE FIELD VERIFIED BY ENGINEER PRIOR TO INSTALLATION.

4. ALL EXCESS WOODY DEBRIS TO BE DISPOSED OF LEGALLY OFFSITE.

5. FOR AREAS TO BE GRADED, TREES, STUMPS AND ROOTS TO BE REMOVED TO A DEPTH OF 12 INCHES (MIN) BELOW FINAL GRADE.

6. HOLES AND TRENCHES REMAINING AFTER GRUBBING TO BE GRADED OR FILLED

7. ANY MERCHANTABLE TIMBER MAY BE CONSIDERED PROPERTY OF THE CONTRACTOR.

8. ECT RECOMMENDS THAT TREE REMOVALS OCCUR OCTOBER 1 THROUGH MARCH 31 WHEN BATS ARE NOT PRESENT. IF THESE CUTTING RESTRICTION DATES CANNOT ME BE, POTENTIAL BAT ROOST TREE SURVEYS MAY BE CONDUCTED AND EQUIPMENT ACCESS ROUTES SELECTED TO AVOID THE IDENTIFIED POTENTIAL ROOSTS

EASTERN MASSASAUGA RATTLESNAKE (EMR) NOTES:

1. CONTRACTOR TO USE WILDLIFE-SAFE MATERIALS FOR EROSION CONTROL AND SITE RESTORATION (MATERIALS THAT DO NOT INCORPORATE PLASTIC-MESH OR OTHER SIMILAR MATERIAL THAT COULD ENSNARE EMR).

2. CONTRACTOR AND SUBCONTRACTORS ON SITE SHOULD WATCH MDNR'S "60-SECOND SNAKES: THE EASTERN MASSASAUGA RATTLESNAKE" VIDEO OR REVIEW THE USFWS EMR FACTSHEET.

CONTRACTOR MUST REPORT ANY EMR OBSERVATIONS, OR OBSERVATION OF ANY OTHER LISTED THREATENED OR ENDANGERED SPECIES, DURING PROJECT IMPLEMENTATION TO ENGINEER WITHIN 2 HOURS.

3 WORKING DAYS **BEFORE YOU DIG** CALL MISS DIG 1-800-482-7171

Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com





ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**


FOR BIDDING EGLE/USACE JOINT PERMIT APP. 06-2020

<u>180611-0300</u> ECT PROJECT NUMBER

AB MB


DESIGNED BY CHECKED BY DRAWN BY APPROVED BY

> **DEMOLITION PLAN**









EXIST. CONTOUR EXIST. STREAM CENTERLINE EXIST.PROPERTY LINE FEMA 100-YR FLOOD BOUNDARY PR. STREAM CENTERLINE PR. GRADING PR. ACCESS ROUTE ---------PR. WETLAND PR. ENHANCED STORMWATER BASIN

PR. HABITAT STRUCTURE

HABITAT STRUCTURES SCHEDULE

STA.	DETAIL	DESCRIPTION
4+90 TO 5+30	2/27	WHOLE TREE REVETMENT - LEFT BANK
5+60 TO 6+05	2/27	WHOLE TREE REVETMENT - RIGHT BANK
6+50	10/27	SCOUR POOL LOG
7+30	9/27	SCOUR POOL LOG
7+70	13/27	WOODY HABITAT
8+45 TO 8+85	2/27	WHOLE TREE REVETMENT - LEFT BANK
8+45 TO 8+85	2/27	WHOLE TREE REVETMENT - RIGHT BANK
9+30	11/27	STAGGERED WING LOGS
10+60	9/27	SCOUR POOL LOG
10+90	13/27	WOODY HABITAT
11+35	10/27	SCOUR POOL LOG
11+80	13/27	WOODY HABITAT
12+50	12/27	HORIZONTAL LOG SILL
12+85 TO 13+25	2/27	WHOLE TREE REVETMENT - RIGHT BANK
14+35 TO 14+75	2/27	WHOLE TREE REVETMENT - RIGHT BANK
15+40	6/27	AT-GRADE RIFFLE
17+10	8/27	ROOTWAD REVETMENT - RIGHT BANK
17+50	7/27	AT-GRADE RIFFLE
18+40 TO 18+60	2/27	WHOLE TREE REVETMENT - RIGHT BANK
19+50	10/27	SCOUR POOL LOG

GENERAL EARTHWORK NOTES:

1. DO NOT PLACE OR COMPACT FILL MATERIAL DURING WET OR FREEZING WEATHER THAT PREVENTS ACHIEVEMENT OF SPECIFIED COMPACTION REQUIREMENTS.

MAINTENANCE AND GUARANTEE PERIOD:

1. CONTRACTOR SHALL GUARANTEE ALL MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FOLLOWING THE APPROVAL OF CONSTRUCTION INSPECTION AT SUBSTANTIAL COMPLETION. THE CONTRACTOR SHALL RESPOND WITHIN TWO WEEKS OF WRITTEN REQUESTS BY THE OWNER FOR REPLACEMENT/REPAIR. IF THE CONTRACTOR FAILS TO RESPOND WITHIN THIS TIME, THE OWNER MAY PROCEED WITH REPLACEMENT WORK AND BILL THE CONTRACTOR.

2. NOTIFY THE OWNER PRIOR TO AND FOLLOWING ANY MAINTENANCE ACTIVITY.

3. FINAL ACCEPTANCE OF WORK WILL BE SUBJECT TO ACCEPTANCE BY PROJECT MANAGER AND OWNER AT THE END OF GUARANTEE PERIOD.

MATERIAL NOTES:

1. ALL MATERIALS SHALL CONFORM TO DETAILS AND SPECIFICATIONS IN THE DRAWINGS.

SUBMITTALS

1. SUBMITTALS FOR APPROVAL BY ENGINEER ARE REQUIRED FOR ALL MATERIALS PRIOR TO MOBILIZATION. ALL EXPENSES INCURRED BY CONTRACTOR PRIOR TO ENGINEER'S APPROVAL SHALL NOT BE PAID BY OWNER.

SITE RESTORATION AND CLEAN-UP:

1. IMMEDIATELY CLEAN UP EXCESS SOIL, MULCH, OR OTHER DEBRIS AND PROPERLY DISPOSE OF DELETERIOUS MATERIALS LEGALLY OFF-SITE IN A MANNER CONSISTENT WITH LOCAL LAWS. TAKE NECESSARY PRECAUTIONS TO PREVENT CONTAMINATION OF CLEAN AREAS AS A RESULT OF CLEANING OPERATIONS.

2. PROMPTLY REMOVE EQUIPMENT AND UNUSED MATERIALS AT COMPLETION OF ACTIVITIES.

3. RETURN STOCKPILE AND STORAGE AREAS TO THEIR ORIGINAL GRADE AND RESTORE GROUND SURFACES AFTER STORED MATERIAL HAS BEEN REMOVED.

4. CONTRACTOR SHALL REPAIR DAMAGED VEGETATION AND AERATE SOIL OVER ROOT ZONE OF NEGATIVELY IMPACTED VEGETATION. RE-SEED ALL DISTURBED AREAS TO PRE-EXISTING CONDITIONS OR AS SPECIFIED.

SITE RESTORATION AND CLEAN-UP:

1. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AS BUILT DOCUMENTS AT THE COMPLETION OF THE WORK. AS-BUILT DRAWINGS SHALL INCLUDE 1 COPY OF MARKED UP FIELD PLANS AND 3 COPIES OF CERTIFIED AS-BUILT DRAWINGS AND 1 DIGITAL FILE CONTAINING AUTOCAD AS-BUILT INFORMATION. THE BASE SURVEY DRAWING WILL BE PROVIDED TO THE CONTRACTOR.

GRADING AND LAYOUT NOTES

1. ALL PROPOSED ELEVATIONS SHOWN ARE FINISHED GRADE. FINAL DESIGN GRADES MAY BE ADJUSTED TO MINIMIZE GRADING

2. CONTRACTOR SHALL PROVIDE GRADE VERIFICATION STAKES AT ALL PROPOSED SPOT ELEVATIONS SHOWN ON THE PLANS AND EVERY 50 FEET ALONG PROPOSED CONTOURS AS DIRECTED BY THE ENGINEER.

3. THE CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING VEGETATION IN AREAS ADJACENT TO WORK AREAS. ALL DISTURBED AREAS SHALL BE REVEGETATED AND RESTORED TO EXISTING CONDITIONS.

4. ALL FILL SHALL BE AS SPECIFIED. ALL IMPORTED FILL SOIL SOURCES SHALL BE APPROVED BY THE ENGINEER IN WRITING PRIOR TO DELIVERY TO THE PROJECT SITE.

3 WORKING DAYS **BEFORE YOU DIG** CALL MISS DIG 1-800-482-7171



Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax







ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**


FOR BIDDING EGLE/USACE JOINT PERMIT APP. 06-2020 180611-0300 ECT PROJECT NUMBER

PROPOSED PLAN -**OVERVIEW**










LEGEND EXIST. CONTOUR -838 EXIST. STREAM CENTERLINE EXIST.PROPERTY LINE EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET **END SECTION** CULVERT EXIST. FENCE EXIST. WETLAND FEMA 100-YR FLOOD BOUNDARY PR. STREAM CENTERLINE PR. THALWEG PR. BOTTOM OF BANK _____ PR. TOP OF BANK PR. CONTOUR

PR. BASIN EXCAVATION AREA

PR. ACCESS ROUTE

PR. WETLAND

INDEX MAP



2200 Commonwealth Blvd, Suite 300 Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com





ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND **RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**

EGLE/USACE JOINT PERMIT APP. <u>180611-0300</u> ECT PROJECT NUMBER


AB MB
DESIGNED BY CHECKED BY AT JO APPROVED BY

PROPOSED PLAN -**ZONE A**

SCALE: 1" = 40' @ 22" x 34"



SHEET NUMBER



2200 Commonwealth Blvd, Suite 300 Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax





ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND **RESTORATION PROJECT**


MICHIGAN

AT JO

DRAWN BY APPROVED BY

PROPOSED PLAN -

SCALE: 1" = 20' @ 22" x 34" SHEET NUMBER



EXIST. CONTOUR

EXIST. STREAM CENTERLINE

EXIST.PROPERTY LINE EXIST. FENCE

FEMA 100-YR FLOOD BOUNDARY PR. STREAM CENTERLINE

PR. THALWEG

PR. BOTTOM OF BANK PR. TOP OF BANK


PR. CONTOUR

PR. ACCESS ROUTE

PR. WETLAND

PR. HABITAT STRUCTURE

INDEX MAP



ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND RESTORATION **PROJECT**

Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com

Working together, restoring the river

SOUTHFIELD, **MICHIGAN**

FOR BIDDING
EGLE/USACE JOINT PERMIT APP.


AT JO

DRAWN BY APPROVED BY

PROPOSED PLAN -**ZONE C**

SCALE: 1" = 20' @ 22" x 34"

N



EXIST. CONTOUR

EXIST. STREAM CENTERLINE

EXIST.PROPERTY LINE EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET

END SECTION CULVERT

EXIST. FENCE

FEMA 100-YR FLOOD BOUNDARY PR. STREAM CENTERLINE

PR. THALWEG

PR. BOTTOM OF BANK _____

> PR. TOP OF BANK PR. CONTOUR


PR. ACCESS ROUTE PR. WETLAND

PR. AT-GRADE RIFFLE

PR. RIP RAP AT CULVERT ENDS -----PR. SILT CURTAIN

PR. HABITAT STRUCTURE

INDEX MAP



Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com OURS TO PROTECT

Working together, restoring the river

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**


> SOUTHFIELD, **MICHIGAN**

EGLE/USACE JOINT PERMIT APP. 180611-0300 ECT PROJECT NUMBER

PROPOSED PLAN -**ZONE D**

N

SHEET NUMBER



EXIST. CONTOUR

EXIST. STREAM CENTERLINE

EXIST.PROPERTY LINE

FEMA 100-YR FLOOD BOUNDARY

PR. STREAM CENTERLINE

PR. GRADING

PR. MAINTENANCE ACCESS ROUTE

PR. WETLAND

Alliance of Rouge Communities OURS TO PROTECT Working together, restoring the river

Ann Arbor, Michigan 48105 734.769.3004



REVEGETATION LEGEND

STORMWATER BASIN:

- STRAW MULCH BLANKET (S75BN, SEE STRAW MULCH BLANKET
- INSTALLATION NOTES)B&B TREES
- 3-5 GAL. CONTAINERIZED SHRUBS
- 4 IN. TOPSOIL
- NATIVE CONNECTION EMERGENT SEED MIX

FLOODPLAIN BENCH:

- ECB (C700BN, SEE ECB INSTALLATION NOTES)
 ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM
- CHANNEL AND STAPLED PER THE MANUFACTURER'S
 RECOMMENDATIONS WITH STAPLE PATTERN "D"
- LIVE STAKES4 IN. TOPSOIL
- NATIVE CONNECTIONS FORESTED WETLAND SEED MIX

FLOODPLAIN SLOPES:

- ECB (NAG C700BN, SEE ECB INSTALLATION NOTES)
- ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM
 CHANNEL AND STAPLED PER THE MANUFACTURER'S
 RECOMMENDATIONS WITH STAPLE PATTERN "D"
- 6 IN. TOPSOIL
- NATIVE CONNECTIONS MESIC WOODLAND SEED MIX

- DISTURBED UPLAND:
 ECB (S75BN, SEE ECB INSTALLATION NOTES)
- 6 IN. TOPSOIL
- MDOT THM SEED MIX

LIVE STAKES:

SEE SHEET 20 FOR DETAILS

SEE SHEET 20 FOR DETAILS.

EROSION CONTROL BLANKET (ECB) INSTALLATION FOR SLOPE OF FLOODPLAIN

INSTALLATION OF ECB TO MATCH MANUFACTURERS INSTRUCTIONS (SHORELINE/ STREAM BANK APPLICATIONS) AND THE FOLLOWING REQUIREMENTS:

- INSTALL ECB AFTER SEEDING, BUT PRIOR TO PLANTING
- INSTALL ECB PERPENDICULAR TO STREAM CHANNEL. ECB TO BE ROLLED FROM TOP OF SLOPE TO BOTTOM OF SLOPE.
- ANCHOR ECB USING A 6 IN. DEEP X 6 IN. WIDE TRENCH WITH APPROX. 12 IN.
 OF ECB EXTENDED BEYOND THE UPSLOPE PORTION OF THE TRENCH.
 ANCHOR ECB WITH A ROW OF STAPLES APPROX. 12 IN. APART IN THE
 BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER
 STAPLING. APPLY SEED TO THE COMPACTED SOIL AND FOLD THE REMAINING
 12 IN. PORTION OF ECB BACK OVER THE SEED AND COMPACTED SOIL.
 SECURE ECB OVER COMPACTED SOIL WITH A ROW OF STAPLES SPACED
- APPROX.12 IN. APART ACROSS THE WIDTH OF THE ECB
 THE EDGES OF ALL HORIZONTAL AND VERTICAL SEAMS MUST BE STAPLED WITH A 2 IN. TO 5 IN. OVERLAP. SEAM OVERLAPS SHOULD BE SHINGLED IN THE STREAM FLOW DIRECTION.
- AN ADEQUATE NUMBER OF STAPLES MUST BE USED TO SECURE ECB.
 STAPLE PATTERN MUST MATCH "STAPLE PATTERN D" WITH MIN. STAPLE
 DENSITY OF 3.4 STAPLES PER SQUARE YARD.

ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN

FOR BIDDING

EGLE/USACE JOINT PERMIT APP.

180611-0300

ECT PROJECT NUMBER


AB

MB

DESIGNED BY

GUEGKED BY

PROPOSED
REVEGETATION
PLAN OVERVIEW






3 WORKING DAYS

BEFORE YOU DIG

CALL MISS DIG

1-800-482-7171



REVEGETATION LEGEND

STORMWATER BASIN:

STRAW MULCH BLANKET (S75BN, SEE STRAW MULCH BLANKET)

INSTALLATION NOTES)

 B&B TREES • 3-5 GAL. CONTAINERIZED SHRUBS

 4 IN. TOPSOIL NATIVE CONNECTION EMERGENT SEED MIX

FLOODPLAIN BENCH:

ECB (C700BN, SEE ECB INSTALLATION NOTES)

 ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM CHANNEL AND STAPLED PER THE MANUFACTURER'S RECOMMENDATIONS WITH STAPLE PATTERN "D"

LIVE STAKES

4 IN. TOPSOIL

NATIVE CONNECTIONS FORESTED WETLAND SEED MIX

FLOODPLAIN SLOPES:

 ECB (NAG C700BN, SEE ECB INSTALLATION NOTES) ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM CHANNEL AND STAPLED PER THE MANUFACTURER'S

RECOMMENDATIONS WITH STAPLE PATTERN "D" • 6 IN. TOPSOIL

NATIVE CONNECTIONS MESIC WOODLAND SEED MIX

DISTURBED UPLAND: ECB (S75BN, SEE ECB INSTALLATION NOTES)

6 IN. TOPSOIL

LIVE STAKES:

MDOT THM SEED MIX

SEE SHEET 20 FOR DETAILS

PLANT LIST: THIS SHEET SEE SHEET 20 FOR DETAILS

IKEES)					
SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING
\odot	32	ACER RUBRUM	RED MAPLE	2.5 - 3" CAL.	B&B	15' O.C.
\odot	57	ACER SACCHARINUM	SILVER MAPLE	2.5 - 3" CAL.	B&B	15' O.C.
	4	CARPINUS CAROLINIANA	MUSCLEWOOD	5-7' HT.	B&B	15' O.C.
	5	CELTIS OCCIDENTALIS	HACKBERRY	2.5 - 3" CAL.	B&B	15' O.C.
	1	PLATANUS OCCIDENTALIS	SYCAMORE	2.5 - 3" CAL.	B&B	15' O.C.
	24	QUERCUS BICOLOR	SWAMP WHITE OAK	2.5 - 3" CAL.	B&B	15' O.C.
	1	QUERCUS MACROCARPA	BUR OAK	2.5 - 3" CAL.	B&B	15' O.C.
	23	QUERCUS PALUSTRIS	PIN OAK	2.5 - 3" CAL.	B&B	15' O.C.

SHRUBS: PLANTED IN 12- PLANT CLUSTERS AS SHOWN

SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING
Co	84	CEPHALANTHUS OCCIDENTALIS	BUTTONBUSH	36" HT.	3-5 GAL.	6' O.C.
Ca	60	CORNUS AMOMUM	SILKY DOGWOOD	36" HT.	3-5 GAL.	6' O.C.
Cf	120	CORNUS FOEMINA	GRAY DOGWOOD	36" HT.	3-5 GAL.	6' O.C.
Cs	144	CORNUS SERICEA	RED-OSIER DOGWOOD	36" HT.	3-5 GAL.	6' O.C.
Hv	84	HAMAMELIS VIRGINIANA	WITCH-HAZEL	36" HT.	3-5 GAL.	6' O.C.
lv	72	ILEX VERTICILLATA	WINTERBERRY	36" HT.	3-5 GAL.	6' O.C.
Lb	96	LINDERA BENZOIN	SPICEBUSH	36" HT.	3-5 GAL.	6' O.C.
Po	12	PHYSOCARPUS OPULIFOLIUS	NINEBARK	36" HT.	3-5 GAL.	6' O.C.
Sc	60	SAMBUCUS CANADENSIS	COMMON ELDERBERRY	36" HT.	3-5 GAL.	6' O.C.
Va	60	VIBURNUM ACERIFOLIUM	MAPLE LEAVED VIBURNUM	36" HT.	3-5 GAL.	6' O.C.
Vd	60	VIBURNUM DENTATUM	ARROW WOOD	36" HT.	3-5 GAL.	6' O.C.
Vt	48	VIBURNUM TRILOBUM	AMERICAN HIGHBUSH CRANBERRY	36" HT.	3-5 GAL.	6' O.C.

LEGEND

EXIST. CONTOUR EXIST. STREAM CENTERLINE

EXIST.PROPERTY LINE

EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET **END SECTION**

CULVERT EXIST. FENCE

EXIST. WETLAND

. FEMA 100-YR FLOOD BOUNDARY

PR. STREAM CENTERLINE PR. THALWEG

PR. BOTTOM OF BANK ____

> PR. TOP OF BANK PR. CONTOUR

PR. ACCESS ROUTE

PR. WETLAND

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

Ann Arbor, Michigan 48105

734.769.3004 734.769.3164 fax


www.ectinc.com

Working together, restoring the river

the center of it all

SOUTHFIELD, **MICHIGAN**

INDEX MAP



3 WORKING DAYS BEFORE YOU DIG CALL MISS DIG 1-800-482-7171


FOR BIDDING EGLE/USACE JOINT PERMIT APP. 180611-0300 ECT PROJECT NUMBER

AB MB
DESIGNED BY CHECKED BY AT DRAWN BY - **JO** APPROVED BY

PROPOSED REVEGETATION PLAN -**ZONE A**

SCALE: 1" = 40' @ 22" x 34"





BEFORE YOU DIG CALL MISS DIG 1-800-482-7171

NORTH (N)

Ann Arbor, Michigan 48105

734.769.3004 734.769.3164 fax www.ectinc.com

Working together, restoring the river

ROUGE RIVER

AOC HABITAT

PROJECT:

TAMARACK

CREEK - STREAM

AND WETLAND

RESTORATION

PROJECT

SOUTHFIELD,

MICHIGAN

FOR BIDDING
EGLE/USACE JOINT PERMIT APP.

DESIGNED BY

DRAWN BY

180611-0300 ECT PROJECT NUMBER

PROPOSED

REVEGETATION

PLAN -

ZONE B


SCALE: 1" = 20' @ 22" x 34"

SHEET NUMBER

APPROVED BY

01-2021

BASE SURVEY CONDUCTED BY MIDWESTERN CONSULTING IN DECEMBER 2018



MATCH LINE SEE SHEET 19

LEGEND

8 EXIST. CONTOUR

EXIST. STREAM CENTERLINE

EXIOT. OTNEAM CENTERE

EXIST.PROPERTY LINE

EXIST. FENCE

FEMA 100-YR FLOOD BOUNDARY

PR. STREAM CENTERLINE

— PR. THALWEG

PR. TOP OF BANK

PR. CONTOUR

PR. BOTTOM OF BANK

PR. MAINTENANCE ACCESS ROUTE

PR. WETLAND

PR. AT-GRADE RIFFLE

REVEGETATION LEGEND

STORMWATER BASIN:

- STRAW MULCH BLANKET (S75BN, SEE STRAW MULCH BLANKET INSTALLATION NOTES)
- B&B TREES
- 3-5 GAL. CONTAINERIZED SHRUBS
- 4 IN. TOPSOIL
- NATIVE CONNECTION EMERGENT SEED MIX

FLOODPLAIN BENCH:

- ECB (C700BN, SEE ECB INSTALLATION NOTES)
 ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM CHANNEL AND STAPLED PER THE MANUFACTURER'S
- RECOMMENDATIONS WITH STAPLE PATTERN "D"

 LIVE STAKES
- 4 IN. TOPSOIL
- NATIVE CONNECTIONS FORESTED WETLAND SEED MIX

FLOODPLAIN SLOPES:

- ECB (NAG C700BN, SEE ECB INSTALLATION NOTES)
- ECB TO BE INSTALLED PERPENDICULAR TO THE STREAM CHANNEL AND STAPLED PER THE MANUFACTURER'S RECOMMENDATIONS WITH STAPLE PATTERN "D"
- 6 IN. TOPSOILNATIVE CONNECTIONS MESIC WOODLAND SEED MIX


.

- ECB (S75BN, SEE ECB INSTALLATION NOTES)
- 6 IN. TOPSOIL

MDOT THM SEED MIX

LIVE STAKES: • SEE SHEET 20 FOR DETAILS

INDEX MAP



3 WORKING DAYS
BEFORE YOU DIG
CALL MISS DIG
1-800-482-7171

EOR BIDDING
EGLE/USACE JOINT PERMIT APP.

180611-0300
ECT PROJECT NUMBER

AB MB
DESIGNED BY CHECKED BY

DRAWN BY APPROVED BY

Ann Arbor, Michigan 48105 734.769.3004

734.769.3164 fax

Working together, restoring the river

ROUGE RIVER

AOC HABITAT

PROJECT:

TAMARACK

CREEK - STREAM

AND WETLAND


RESTORATION

PROJECT

SOUTHFIELD,

MICHIGAN

PROPOSED
REVEGETATION
PLAN ZONE C




NORTH SHEET NO.

BASE SURVEY CONDUCTED BY MIDWESTERN CONSULTING IN DECEMBER 2018

1 PROPOSED REVEGETATION PLAN - ZONE C

MATCH LINE SEE SHEET 19

18 SCALE: 1" = 20' @ 22" x 34"




LEGEND EXIST. CONTOUR EXIST. STREAM CENTERLINE EXIST.PROPERTY LINE EXIST. STORM SEWER EXIST. CATCH BASIN OR INLET **END SECTION** CULVERT EXIST. FENCE FEMA 100-YR FLOOD BOUNDARY PR. STREAM CENTERLINE PR. THALWEG PR. BOTTOM OF BANK _____ PR. TOP OF BANK PR. CONTOUR PR. ACCESS ROUTE PR. WETLAND PR. AT-GRADE RIFFLE

INDEX MAP

PR. RIP RAP AT CULVERT ENDS

PR. SILT CURTAIN



PLANT LIST: THIS SHEET SEE SHEET 20 FOR DETAILS

TREES	REES						
SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING	
	2	QUERCUS MACROCARPA	BUR OAK	2.5 - 3" CAL.	B&B	15' O.C.	
	2	TILIA AMERICANA	BASSWOOD	2.5 - 3" CAL.	B&B	15' O.C.	

SHRUBS: PLANTED IN 12- PLANT CLUSTERS AS SHOWN

SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING
Cs	12	CORNUS SERICEA	RED-OSIER DOGWOOD	36" HT.	3-5 GAL.	6' O.C.
Sc	12	SAMBUCUS CANADENSIS	COMMON ELDERBERRY	36" HT.	3-5 GAL.	6' O.C.
Vt	12	VIBURNUM TRILOBUM	AMERICAN HIGHBUSH CRANBERRY	36" HT.	3-5 GAL.	6' O.C.

Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax

OURS TO PROTECT Working together, restoring the river



ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**


EGLE/USACE JOINT PERMIT APP. 180611-0300 ECT PROJECT NUMBER

PROPOSED

REVEGETATION PLAN -**ZONE D**

SCALE: 1" = 20' @ 22" x 34"





1. INSTALL IN MUDFLAT/TILL ZONE AS DIRECTED BY LANDSCAPE ECOLOGIST, DURING FIRST DORMANT SEASON FOLLOWING SEEDING

2. INSTALL LIVE STAKES AT RIGHT ANGLES PUSH INTO THE GROUND BY HAND. DEAD BLOW HAMMER AND PILOT HOLES AS NECESSARY.

3. BURY FOUR-FIFTHS OF THE STAKE IN THE GROUND, AND FIRMLY PACK SOIL AROUND IT ORIENT THE BUDS UP.


4. INSTALL STAKES 3 FEET APART IN TRIANGULAR SPACING PATTERN. SEE DETAIL 6 ON SHEETS 28 FOR INSTALLATION LOCATION ON

LIVE STAKE INSTALLATION

NO SCALE

- SHRUB SHALL BEAR SAME OR SLIGHTLY HIGHER RELATION TO FINISH GRADE AS TO PRIOR GRADE - NEVER LOWER
- 2. PRUNE ONLY AS DIRECTED EXCEPT FOR REMOVING DEAD OR BROKEN BRANCHES; RETAIN NATURAL FORM.
- 3. PLANT SHRUBS WITH MAIN LEADER PERPENDICULAR TO THE GROUND SURFACE.

4. IF NO EROSION CONTROL FIBER IS REQUIRED, MULCH 3-4' AROUND BASE OF SHRUB.



OVERALL PLANT LIST

IG PLANT TOTALS FROM SHEETS 16-19

REP	RES	EN	TIN	10
TRE	ES			

	<u>'</u>					
SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING
\odot	80	ACER RUBRUM	RED MAPLE	2.5 - 3" CAL.	B&B	15' O.C.
0	100	ACER SACCHARINUM	SILVER MAPLE	2.5 - 3" CAL.	B&B	15' O.C.
8	27	ACER SACCHARUM	SUGAR MAPLE	2.5 - 3" CAL.	B&B	15' O.C.
63	39	CARPINUS CAROLINIANA	MUSCLEWOOD	5-7' HT.	B&B	15' O.C.
\oplus	59	CELTIS OCCIDENTALIS	HACKBERRY	2.5 - 3" CAL.	B&B	15' O.C.
0	39	PLATANUS OCCIDENTALIS	SYCAMORE	2.5 - 3" CAL.	B&B	15' O.C.
0	24	QUERCUS BICOLOR	SWAMP WHITE OAK	2.5 - 3" CAL.	B&B	15' O.C.
O	25	QUERCUS MACROCARPA	BUR OAK	2.5 - 3" CAL.	B&B	15' O.C.
6	23	QUERCUS PALUSTRIS	PIN OAK	2.5 - 3" CAL.	B&B	15' O.C.
€€	38	TILIA AMERICANA	BASSWOOD	2.5 - 3" CAL.	B&B	15' O.C.

CUBURC: DI ANTED IN 42 DI ANT CILICTEDE AC CHOMA

SHRU	SHRUBS: PLANTED IN 12- PLANT CLUSTERS AS SHOWN						
SYM	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	CONT.	SPACING	
Co	84	CEPHALANTHUS OCCIDENTALIS	BUTTONBUSH	36" HT.	3-5 GAL.	6' O.C.	
Ca	168	CORNUS AMOMUM	SILKY DOGWOOD	36" HT.	3-5 GAL.	6' O.C.	
Cf	240	CORNUS FOEMINA	GRAY DOGWOOD	36" HT.	3-5 GAL.	6' O.C.	
Cs	252	CORNUS SERICEA	RED-OSIER DOGWOOD	36" HT.	3-5 GAL.	6' O.C.	
Hv	180	HAMAMELIS VIRGINIANA	WITCH-HAZEL	36" HT.	3-5 GAL.	6' O.C.	
lv	132	ILEX VERTICILLATA	WINTERBERRY	36" HT.	3-5 GAL.	6' O.C.	
Lb	216	LINDERA BENZOIN	SPICEBUSH	36" HT.	3-5 GAL.	6' O.C.	
Po	72	PHYSOCARPUS OPULIFOLIUS	NINEBARK	36" HT.	3-5 GAL.	6' O.C.	
Sc	108	SAMBUCUS CANADENSIS	COMMON ELDERBERRY	36" HT.	3-5 GAL.	6' O.C.	
Va	168	VIBURNUM ACERIFOLIUM	MAPLE LEAVED VIBURNUM	36" HT.	3-5 GAL.	6' O.C.	
Vd	96	VIBURNUM DENTATUM	ARROW WOOD	36" HT.	3-5 GAL.	6' O.C.	
Vt	120	VIBURNUM TRILOBUM	AMERICAN HIGHBUSH CRANBERRY	36" HT.	3-5 GAL.	6' O.C.	

NOTES: TREE SHALL BE PLANTED WITH TOP OF ROOT BALL AT OR SLIGHTLY ABOVE FINISH GRADE - NEVER LOWER.

PRUNE ONLY AS DIRECTED EXCEPT FOR REMOVING DEAD OR BROKEN BRANCHES: RETAIN NATURAL FORM; DO NOT CUT LEADER.

4" MULCH TO COVER — **ENTIRE PLANTING** HOLE. TAPER MULCH TO TRUNK. CREATE CONTINUOUS 6" EARTH SAUCER.

SPECIFIED-BACKFILL SOIL

DECIDUOUS TREE PLANTING

REMOVE TOP 1/3 OF BURLAP OR **ENTIRE RAP IF** NON-BIODEGRADEABLE AFTER PLACING TREE IN PIT SCARIFY BOTTOM

AND SIDEWALLS OF PLANTING PIT.

Native Connections | 17080 Hoshel Rd, Three Rivers, MI 49093 | www.nativeconnections.net

Bristly Sedge

Fox Sedge

Soft Rush

Torrey's Rush

Rice Cut Grass

Wool Grass

River Bulrush

Soft-stem Bulrush

Swamp Milkweed

Nodding Bur Marigold

Swamp Aster

Water Hemlock

Joe Pye Weed

Blue Flag Iris

Cardinal Flower

Monkey Flower

Ditch Stonecrop

Pickerel Weed

Blue Vervain

Seed Oats

Great Water Dock

Common Arrowhead

Common Bur Reed

Annual Ryegrass

Pennsylvania Smartweed

Arrow Arum

Great Blue Lobelia

Boneset

Common Water Plantain

Hard-stem Bulrush

Dark Green Bulrush

Fringed Sedge

Porcupine Sedge

Awl-fruited Sedge

Great Spike Rush

Canada Manna Grass

Reed Manna Grass

EMERGENT WETLAND SEED MIX

Total Seeding Rate: 31.25 lbs per acre

GRASSES, SEDGES & RUSHES

Carex comosa

Carex crinita

Carex stipata

Carex hystericina

Carex vulpinoidea

Eleocharis palustris

Glyceria canadensis

Glyceria grandis

Juncus effusus

Juncus torreyi

Scirpus acutus

Leersia oryzoides

Scirpus atrovirens

Scirpus cyperinus

Scirpus fluviatilis

Acorus americanus

Alisma subcordatum

Asclepias incarnata

Aster puniceus

Bidens cernua

Cicuta maculata

Eupatorium maculatum

Eupatorium perfoliatum

Iris virginica Southern

Lobelia cardinalis

Lobelia siphilitica

Mimulus ringens

Peltandra virginica

Pontederia cordata

Rumex orbiculatus

Sagittaria latifolia

Verbena hastata

Lolium multiflorum

Total Temp Grasses

Avena sativa

Total Forbs

Penthorum sedoides

Polygonum pensylvanicum

Sparganium eurycarpum


TEMPORARY GRASS COVER

Scirpus validus

Total Grasses

FORBS

6" EARTH PEDESTAL OF UNDISTURBED OR COMPACTED SOIL. SLOPE TREE PLANTING



STEEL T-POST SPACED TO AVOID ROOTBALL INSTALL IN VERTICAL POSITION-SET PLUMB. DRIVE A MINIMUM 12" INTO UNDISTURBED SOIL. TREE WRAP FROM BASE TO FIRST —— REMOVE TOP 1/3 OF BURLAP OR ENTIRE RAP IF NON-BIODEGRADEABLE.

1. TREE SHALL BEAR SAME OR SLIGHTLY HIGHER RELATION

2. CREATE HORIZONTAL SHELF FOR TREE WHEN PLANTING

PRUNE ONLY AS DIRECTED EXCEPT FOR REMOVING

DEAD OR BROKEN BRANCHES; RETAIN NATURAL FORM;

ON A SLOPE. DO NOT FILL OVER ROOT BALL ON

4. BRACE ALL DECIDUOUS TREES UP TO 4" WITH TWO

UPSLOPE.

STAKES.

RIDGES OF T-POST

20 NOT TO SCALE

PLS OZ/ACRE SEEDS/SQ F

3.44

0.53

2.75

1.56

9.18

0.29

3.40

7.35

5.74

9.18

1.56

0.46

10.56

9.76

0.69

1.42

67.88

0.76

4.82

0.22

0.92

0.48

0.21

0.55

1.84

0.05

2.30

2.87

13.20

0.01

14.92

0.90

0.17

0.05

0.35

0.09

4.27

48.95

30.99

7.35

38.34

SEEDS/SQ F

PLS OZ/ACRE SEEDS/SQ F

5.00

1.00

4.00

2.00

4.00

0.25

2.00

4.00

0.25

0.25

2.00

1.00

1.00

0.25

7.00

2.00

2.00

0.50

1.00

0.75

0.25

0.50

2.00

0.25

0.25

0.25

8.00

0.50

3.00

6.00

0.25

0.25

7.75

2.00

44.00

100.00

320.00

420.00

OZ/ACRE

36.00

BRANCH.

DO NOT CUT LEADER.

#11 GALVANIZED WIRE WRAPPED

ONE REVOLUTION AND BETWEEN

3"-4" MULCH TO COVER ENTIRE

ON SITES WITHOUT IRRIGATION.

PLANTING HOLE. TAPER MULCH TO

TRUNK. CREATE 6" EARTH SAUCER

TO FINISH GRADE AS TO PRIOR GRADE - NEVER LOWER.

SCARIFY BOTTOM AND SIDEWALLS OF PLANTING PIT.

PLANTING MIXTURE

6" EARTH PEDESTAL OF UNDISTURBED OR COMPACTED SOIL.

> SHRUB PLANTING DETAIL NOT TO SCALE

PLANT ALL SHRUBS VERTICAL

PRUNE ALL DEAD OR DAMAGED BRANCHES —

4" BARK MULCH TO COVER ENTIRE PLANTING —

PROVIDE 3" SOIL SAUCER AROUND EACH PLANT—

BACKFILL WITH MIX OF 50% IMPORTED TOPSOIL-

AND 50% EXCAVATED SITE SOIL & TAMP LIGHTLY

WATER TO SATURATE BACKFILL MATERIAL

IF CONTAINER STOCK IS ROOT BOUND, MAKE

4 VERTICAL CUTS IN EACH ROOT BALL WITH

SCARIFY BOTTOM AND SIDEWALLS OF PLANTING PIT.

WITH IN 8 HOURS OF PLANTING

SHARP BLADE

HOLE. TAPER MULCH TO BASE OF PLANT

Native Connections | 17080 Hoshel Rd, Three Rivers, MI 49093 | www.nativeconnections.net FORESTED WETLAND ESTABLISHMENT SEED MIX

Total Seeding Rate: 31 lbs per acre GRASSES, SEDGES & RUSHES PLS OZ/ACRE SEEDS/SQ FT Bromus ciliatus Fringed Brome 8.00 1.84 Calamagrostis canadensis Bluejoint Grass 0.50 3.21 2.00 Carex comosa **Bristly Sedge** 1.38 2.00 0.78 Carex frankii Frank's Sedge Carex stipata Awl-fruited Sedge 2.00 1.56 Fox Sedge Carex vulpinoidea 4.59 0.64 Elymus riparius Riverbank Wild Rye 4.00 50.00 Virginia Wild Rye 4.82 Elymus virginicus 1.00 Glyceria striata Fowl Manna Grass 3.67 Soft Rush 0.30 Juncus effusus 6.89 0.20 Wool Grass 7.81 Scirpus cyperinus 72.00 **Total Grasses** 37.19

PLS OZ/ACRE SEEDS/SQ FT **FORBS** 0.36 1.75 Actinomeris alternifolia Wingstem Angelica 2.25 0.28 Angelica atropurpurea Aster novae-angliae New England Aster 0.25 0.38 0.25 Aster puniceus Swamp Aster 0.46 0.25 0.03 Bidens frondosa Devil's Beggarticks False Aster 0.50 Boltonia asteroides 0.12 3.75 Cassia hebecarpa Wild Senna 1.30 0.37 Cephalanthus occidentalis Buttonbush 0.50 1.84 Eupatorium perfoliatum Boneset 3.00 8.95 Helenium autumnale Sneezeweed Southern Blue Flag Iris 0.75 Iris virginica 0.02 Lobelia siphilitica 0.25 2.87 Great Blue Lobelia 0.25 1.61 Ludwigia alternifolia Seedbox 0.25 13.20 Monkey Flower Mimulus ringens 1.50 2.41 Monarda fistulosa Wild Bergamot Penstemon digitalis Foxglove Beardtongue 1.20 3.58 1.00 0.25 Obedient Plant Physostegia virginiana Golden Glow 1.50 0.48 Rudbeckia laciniata 1.00 2.53 Solidago ohioensis Ohio Goldenrod 2.50 0.63 Zizia aurea Golden Alexander Total Forbs 24.00 42.21

TEMPORARY GRASS COVER OZ/ACRE SEEDS/SQ FT Annual Ryegrass 80.00 24.79 Lolium multiflorum 320.00 7.35 Avena sativa 400.00 32.14 Total Temp Grasses

Г							
	Native Connections 17080 Hoshel Rd, Three Rivers, MI 49093 www.nativeconnections.net						
	MESIC WOODLAND SEED MIX						
	Total Seeding Rate: 31 lbs per a						
	GRASSES, SEDGES & RUSHE			SEEDS/SQ FT			
	Bromus purgans	Hairy Wood Chess	3.00	0.52			
	Carex cristatella	Crested Sedge	0.50	0.68			
	Carex grayi	Common Bur Sedge	1.75	0.05			
	Carex sprengelii	Long-beaked Sedge	0.50	0.11			
	Elymus villosus	Silky Wild Rye	6.00	0.76			
ı	Elymus virginicus	Virginia Wild Rye	40.00	3.86			
ı	Glyceria striata	Fowl Manna Grass	2.00	7.35			
ı	Hystrix patula	Bottlebrush Grass	6.00	1.05			
ı	Juncus tenuis	Path Rush	0.25	5.74			
١	Total Grasses		60.00	20.11			
	FORBS PLS OZ/ACRE SEEDS/	/SQ FT					
l	Allium tricoccum	Wild Leek	2.00	0.06			
١	Anemone canadensis	Canada Thimbleweed	1.00	0.18			
١	Aquilegia canadensis	Wild Columbine	0.50	0.44			
١	Arisaema triphyllum	Jack-in-the-Pulpit	1.00	0.01			
ı	Blephilia hirsuta	Hairy wood mint	0.25	1.38			
ı	Campanula americana	Tall Bellflower	0.25	0.98			
ı	Caulophyllum thalictroides	Blue Cohosh	4.00	0.01			
١	Eupatorium purpureum	Sweet Joe Pye Weed	2.00	1.93			
١	Eupatorium rugosum	White Snakeroot	0.50	1.72			
١	Geranium maculatum	Wild Geranium	0.25	0.03			
l	Helianthus grosseserratus	Saw-toothed Sunflower	1.00	0.34			
l	Impatiens capensis	Spotted Touch-me-not	0.25	0.02			
l	Lobelia siphilitica	Great Blue Lobelia	0.25	2.87			
l	Penstemon digitalis	Foxglove Beardtongue	2.00	5.97			
l	Polygonatum canaliculatum	Great Solomon's Seal	1.00	0.02			
l	Rudbeckia laciniata	Golden Glow	5.00	1.61			
l	Rudbeckia triloba	Brown-eyed Susan	5.00	3.90			
l	Smilacina racemosa	False Solomon's Seal	4.00	0.04			
١	Solidago caesia	Blue-stemmed Goldenro	od 0.25	3.14			
١	Solidago flexicaulis	Zigzag Goldenrod	0.10	0.19			
	Solidago rugosa	Rough Goldenrod	0.30	0.64			
	Thalictrum dioicum	Early Meadow Rue	0.10	0.02			
	Zizia aurea	Golden Alexander	5.00	1.26			
	Total Forbs		36.00	26.75			
	TEMPORARY GRASS COVER		OZ/ACRE SEE	DS/SQ FT			
	Lolium multiflorum	Annual Ryegrass	80.00	24.79			
	Avena sativa	Seed Oats	320.00	7.35			
- 1							

400.00

32.14

Total Temp Grasses

MDOT THM SEED MIX Total Seeding Rate: 5 LBS. per 1000 SFT – 220 LBS. per ACRE

QUANTITY VARIETY **PURITY** MIN. GERM 50% Creeping Red Fescue 98.5% 85% 30% Kentucky Bluegrass 98.5% 85% 20% Perennial Ryegrass 99.5% 90%

LIVE STAKE SPECIES LIST (2250 TOTAL): SCIENTIFIC NAME **COMMON NAME CORNUS SERICEA** RED-OSIER DOGWOOD **CORNUS AMOMUM** SILKY DOGWOOD SANDBAR WILLOW SALIX EXIGUA SALIX DISCOLOR **PUSSY WILLOW** SALIX SERICEA **SILKY WILLOW** SALIX NIGRA **BLACK WILLOW** SALIX AMYGDALOIDES PEACH-LEAF WILLOW

LISTED SPECIES ARE TO BE EQUALLY REPRESENTED. PLANT LIVE STAKES IN 2 ROWS OF LIVE STAKES AT 36" O.C., STAGGER ROWS. SAME SPECIES IN MINIMUM GROUPS OF 10. Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com

DURS TO PROTECT Working together, restoring the river

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM AND WETLAND RESTORATION PROJECT**

> **SOUTHFIELD MICHIGAN**

01-2021

EGLE/USACE JOINT PERMIT APP. 06-2020 180611-0300 ECT PROJECT NUMBER

FOR BIDDING

DRAWN BY APPROVED BY

PROPOSED REVEGETATION DETAILS

SCALE: AS SHOWN @ 22" x 34"



3 WORKING DAYS

BEFORE YOU DIG

CALL MISS DIG

1-800-482-7171

REVEGETATION NOTES:

MAINTENANCE AND WARRANTY PERIOD:

- 1. WARRANTY PERIOD: WARRANT THAT ALL TREES, SEEDING, AND LIVE STAKES INSTALLED UNDER THIS CONTRACT WILL BE HEALTHY AND IN FLOURISHING CONDITION OF ACTIVE GROWTH FOR ONE (1) FULL GROWING SEASON (APRIL THROUGH NOVEMBER) FROM DATE OF FINAL ACCEPTANCE. THE CONTRACTOR SHALL RESPOND WITHIN TWO (2) WEEKS OF WRITTEN REQUESTS BY THE OWNER FOR REPLACEMENT OR REPAIR. IF THE CONTRACTOR FAILS TO RESPOND WITHIN THIS TIME, THE OWNER MAY PROCEED WITH REPLACEMENT WORK AND BILL THE CONTRACTOR.
- 2. ALL DELAYS IN COMPLETION OF PLANTING OPERATIONS WHICH EXTEND THE PLANTING INTO MORE THAN ONE PLANTING SEASON SHALL EXTEND THE WARRANTY PERIOD CORRESPONDINGLY.
- 3. REPLACEMENTS: AS SOON AS WEATHER CONDITIONS PERMIT, REPLACE, WITHOUT COST TO OWNER, ALL DEAD PLANTS AND ALL PLANTS NOT IN A VIGOROUS, THRIVING CONDITION, AS DETERMINED BY THE CONSULTANT DURING AND AT THE END OF THE WARRANTY PERIOD.
- 4. PATCHY OR BARE AREAS (IN EXCESS OF 8 SQUARE FEET) WHERE SEED MIX FAILED TO CREATE SUFFICIENT DENSITY OF COVER SHALL BE RESEEDED BY HAND AT THE RECOMMENDED APPLICATION RATE AT NO ADDITIONAL COST TO OWNER.
- 5. INCORRECT MATERIALS: DURING WARRANTY PERIOD. REPLACE AT NO COST TO OWNER ALL PLANTS REVEALED AS BEING UNTRUE TO NAME. PROVIDE REPLACEMENTS OF A SIZE AND QUALITY TO MATCH THE PLANTED MATERIALS AT THE TIME THE MISTAKE IS DISCOVERED.
- 6. ALL PLANT STOCK SHALL BE WATERED BY THE CONTRACTOR TO ENSURE THE HEALTH AND VIGOR OF THE PLANTED MATERIALS. THE CONTRACTOR SHALL WATER AS NEEDED BASED ON NATURAL RAINFALL DURING THE WARRANTY PERIOD. WATERING SHALL CONTINUE SO SEEDLINGS DO NOT DRY OUT ONCE WATERING HAS BEGUN. THE WATERING SHALL BE DONE FROM SURFACE METHODS AT A PRESSURE NOT TO EXCEED THE INFILTRATION RATE OF THE SOIL, LIMITING RUNOFF DURING THE WATERING PERIOD. EACH AREA WILL BE WATERED WITH SUFFICIENT WATER TO COMPLETELY SATURATE THE ROOT ZONE. THE CONTRACTOR SHALL INSPECT
- ALL PLANTS FOR INSECT INFESTATION AND DAMAGE. 7. EROSION SHALL BE REPAIRED BY THE CONTRACTOR.
- 8. PROTECTION FROM TRAFFIC AND EROSION IN NEWLY SEEDED AREAS AND THE MITIGATION AREAS IS THE RESPONSIBILITY OF THE CONTRACTOR. SAFETY FENCES AND/OR OTHER BARRIER METHODS WITH APPROPRIATE SIGNAGE MAY BE USED FOR ONE YEAR FROM COMPLETION OF CONSTRUCTION ACTIVITIES. ALL COSTS ASSOCIATED WITH THIS IS INCLUSIVE OF CONTRACTOR'S PRICING.
- NOTIFY THE OWNER PRIOR TO AND FOLLOWING ANY MAINTENANCE ACTIVITY.
- 10. FINAL ACCEPTANCE OF WORK WILL BE SUBJECT TO ACCEPTANCE BY PROJECT MANAGER AND OWNER AT THE END OF GUARANTEE PERIOD.

NATIVE PLANTINGS:

1. TREES AND LIVE STAKES SHALL BE OF NATIVE PLANT MATERIAL OF GENOTYPES FROM THE NORTH CENTRAL STATES ONLY (IL. IN. IA, MI, OH), AND FROM A RECOGNIZED NURSERY OF THIS REGION. MICHIGAN SOURCES FOR TREE, SHRUBS, AND PLUGS SHALL BE LOCATED BEFORE BRANCHING OUT TO OTHER NORTH CENTRAL STATES. NATIVE PLANTINGS INCLUDE ALL TREES AND LIVE STAKES INSTALLED AS PART PF THIS PROJECT.

2. PLANTS SHALL BE NURSERY GROWN IN ACCORDANCE WITH GOOD HORTICULTURAL PRACTICES AND MUST MEET APPLICABLE REQUIREMENTS OF ICBN AND ICNCP. PLANTS SHALL BE SOUND, HEALTHY AND VIGOROUS, WELL BRANCHED AND DENSELY FOLIATED WHEN IN LEAF. PLANTS SHALL BE FREE OF DISEASE, INSECT PESTS, EGGS, OR LARVAE. PLANTS SHALL BE FREE OF KINKED, CIRCLING OR GIRDLING TRUNK SURFACE AND CENTER ROOTS, AND SHALL NOT BE ROOT-BOUND. RESPECT MAXIMUM STORAGE TIMES FOR PLANT STOCK.

3. NATIVE PLANTING AREAS SHALL BE INSTALLED AFTER MAY 15 (WHEN SOIL IS FREE OF FROST AND IN WORKABLE CONDITION), BUT BEFORE JUNE 30 OR AFTER SEPT. 1 BUT BEFORE OCTOBER 30 OR AS APPROVED BY THE ENGINEER.

4. FURNISH PLANT SPECIES AND SIZES AS INDICATED ON THE PLANS. PLANT STOCK SHALL BE TRUE TO THEIR NAME (GENUS AND SPECIES). AS SPECIFIED. CULTIVARS AND SPECIMENS SHALL NOT BE USED WITHOUT PRIOR APPROVAL BY CONSULTANT. 5. NATIVE PLANTINGS TO BE INSTALLED PER DETAILS.

6. REMOVE ALL CONTAINERS AND PACKAGING MATERIAL AND DISPOSE OF LEGALLY OFF-SITE.

AS-BUILT PLAN AND SUBMITTED TO THE CONSULTANT UPON COMPLETION.

7. WATER PLANT STOCK IMMEDIATELY AFTER PLANTING SUCH THAT ROOT ZONE IS THOROUGHLY SOAKED. CONTRACTOR SHALL BE RESPONSIBLE TO KEEP PLUGS ADEQUATELY WATERED, IF NECESSARY, TO ENSURE THEIR SURVIVAL.

8. IF EROSION CONTROL BLANKET IS NEEDED IN AREAS WHERE PLUGS ARE PRESENT. INSTALL EROSION CONTROL BLANKET AFTER SEEDING, BUT PRIOR TO PLANTING. EROSION CONTROL BLANKET SHALL BE INSTALLED WHERE THE CONTRACTOR FEELS IT NECESSARY TO STABILIZE THE SITE AT NO ADDITIONAL COST TO THE OWNER.

9. FIELD ADJUST PLANTINGS TO DIVERSIFY SPECIES ACROSS THE PLANTING AREAS AND TO MEET FINISH GRADE OF THE STREAMBANKS WITH PLANTING REQUIREMENTS FOR SPECIES BASED ON DEPTH. ANY ADJUSTMENTS WILL BE SHOWN ON AN

10. MULCH FOR TREES SHALL BE COARSE GRADE OAK OR MAPLE BARK AGED AT LEAST ONE YEAR AND UNIFORM IN COLOR AND TEXTURE.

1. SEED SHALL BE FRESH, CLEAN, NEW SEED OF NATIVE PLANT MATERIAL OF GENOTYPES FROM THE NORTH CENTRAL STATES ONLY (IL, IN, IA, MI, OH), AND FROM A RECOGNIZED NURSERY OF THIS REGION.

2. NATIVE SEED AREAS SHALL BE SEEDED AFTER MAY 1. (WHEN SOIL IS FREE OF FROST AND IN WORKABLE CONDITION), BUT BEFORE JUNE 30 OR AFTER OCTOBER 1, BUT BEFORE NOVEMBER 30 (OR PRIOR TO FREEZE-UP) OR AS APPROVED BY THE ENGINEER. 3. SEEDBED PREPARATION: CUT ANY EXISTING VEGETATION TO 4 (FOUR) INCH HEIGHT AND APPLY HERBICIDE AS NECESSARY. PRIOR TO SOWING NATIVE SEED, LIGHTLY SCARIFY SO THAT THE BED IS SMOOTH AND FREE OF LARGE CLUMPS. SEED BED SHALL BE FIRM.

4. ALL SEEDED AREAS SHALL BE HYDROSEEDED. A HYDROMULCH CONSISTING OF CELLULOSE OR SIMILAR MULCH WITH TACKIFIER SUITABLE FOR HYDROSEEDING SHALL BE USED AS A SEEING METHOD. NO STRAW MULCH SHALL BE USED.

5. ALL WATER USED IN HYDROMULCH SHALL BE FREE OF SUBSTANCES DETRIMENTAL TO PLANT GROWTH AND SHALL BE SUITABLE FOR DISCHARGE INTO SURFACE WATERS BASED ON LOCAL. STATE, AND FEDERAL REGULATORY REQUIREMENTS. SEEDING METHOD SHALL ENSURE COMPLETE COVERAGE OF DESIGNATED AREA. RE-SEED AREAS WITH GAPS IN SEEDING AT NO ADDITIONAL COST TO OWNER.

6. DO NOT SOW SEED WHERE STANDING WATER IS PRESENT.

BUT NOT COMPACT. SEED IMMEDIATELY AFTER SCARIFYING. DO NOT FERTILIZE.

7. SOW NATIVE SEED AT A SPECIES RATE OF POUNDS PER ACRE INDICATED ON THE DRAWING. LIGHTLY RAKE TO INCORPORATE SEED INTO SOIL. DO NOT COVER SEED MORE THAN 1/4 INCH WITH SOIL. SEED DRILLING IS ALSO ACCEPTABLE.

8. CONTRACTOR SHALL REPAIR DAMAGED VEGETATION AND AERATE SOIL OVER ROOT ZONE OF NEGATIVELY IMPACTED VEGETATION. RE-SEED ALL DISTURBED AREAS TO PRE-EXISTING CONDITIONS.

EXISTING SITE CONDITIONS:

1. CONTRACTOR SHALL BECOME FAMILIAR WITH ALL EXISTING SITE CONDITIONS PRIOR TO STARTING WORK.

- 2. THE CONTRACTOR UNDERSTANDS AND ACKNOWLEDGES THAT THE PERFORMANCE OF THE WORK IS REQUIRED WITHIN A RIVER SYSTEM AND FLOODPLAIN.
- 3. THE CONTRACTOR SHALL BE FULLY AWARE OF THE ROUGE RIVER HYDROLOGY AND CURRENT WEATHER CONDITIONS SO THAT WORK IN PROGRESS CAN BE SECURED AND PROTECTED. SO THAT SAFE JOB SITE WORKING CONDITIONS ARE MAINTAINED. AND SO THAT SOIL EROSION IS MINIMIZED DURING AND FOLLOWING A RAIN EVENT.
- 4. ROUGE RIVER/ TAMARACK CREEK HAS A VERY SHORT RESPONSE TIME TO STORM RUNOFF.
- 5. THE CONTRACTOR ACKNOWLEDGES THAT DELAYS IN THE START OF OR COMPLETION OF WORK DUE TO TYPICAL SEASONAL RAINFALL AND DUE TO TYPICAL PERIODIC HIGH FLOWS IN THE ROUGE RIVER SHALL NOT CONSTITUTE A BASIS FOR ANY EXTENSION OF TIME OR DAMAGES. IF THE CONTRACTOR SHALL BE UNAVOIDABLY DELAYED IN BEGINNING OR FULFILLING THIS CONTRACT BY REASONS OF EXCESSIVE STORM OR FLOODS THE CONTRACTOR SHALL HAVE NO VALID CLAIM FOR DAMAGES, BUT HE SHALL IN SUCH CASE BE ENTITLED TO AN EXTENSION OF TIME AS THE ENGINEER SHALL ADJUDGE TO BE JUST AND REASONABLE; PROVIDED THAT FORMAL CLAIM FOR AN EXTENSION OF TIME IS MADE IN WRITING BY THE CONTRACTOR WITHIN ONE WEEK OF THE ALLEGED DELAY.

Ann Arbor, Michigan 48105 734.769.3004

734.769.3164 fax

www.ectinc.com

Alliance of Rouge Communities **OURS TO PROTECT** Working together, restoring the river



ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK** CREEK - STREAM AND WETLAND **RESTORATION PROJECT**

> SOUTHFIELD. MICHIGAN

EGLE/USACE JOINT PERMIT APP.


180611-0300 ECT PROJECT NUMBER

PROPOSED REVEGETATION DETAILS

SCALE: AS SHOWN @ 22" x 34"

(N

SHEET NUMBER



Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com Working together, restoring the river

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND **RESTORATION PROJECT**


> SOUTHFIELD, **MICHIGAN**

<u>180611-0300</u> ECT PROJECT NUMBER DESIGNED BY CHECKED BY

CROSS-SECTIONS

SCALE AS SHOWN





Environmental Consulting & Technology, Inc. 2200 Commonwealth Blvd, Suite 300 Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com





ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN

FOR BIDDING 01-2021
EGLE/USACE JOINT PERMIT APP. 06-2020

AB MB


DESIGNED BY CHECKED BY

AB/ AK
DDAWN BY APPROVED BY

CROSS-SECTIONS (2/3)

SCALE AS SHOWN





Southfield the center of it all TM

OURS TO PROTECT

Working together, restoring the river

2200 Commonwealth Blvd, Suite 300 Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax

www.ectinc.com

ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN

FOR BIDDING 01-2021
EGLE/USACE JOINT PERMIT APP. 06-2020

 180611-0300

 ECT PROJECT NUMBER

 AB
 MB


 DESIGNED BY
 CHECKED BY

AB/ AK JO
DRAWN BY APPROVED

CROSS-SECTIONS (3/3)

SCALE AS SHOWN





Ann Arbor, Michigan 48105 734.769.3004 734.769.3164 fax www.ectinc.com Working together, restoring the river

ROUGE RIVER AOC HABITAT PROJECT: **TAMARACK CREEK - STREAM** AND WETLAND **RESTORATION PROJECT**

> SOUTHFIELD, **MICHIGAN**


FOR BIDDING
EGLE/USACE JOINT PERMIT APP. 180611-0300 ECT PROJECT NUMBER AB MB

DESIGNED BY CHECKED BY AB/ AK JO
DRAWN BY APPROVED BY

> **STREAM PROFILE** (1/2)

SCALE AS SHOWN







ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN

FOR BIDDING 01-2021
EGLE/USACE JOINT PERMIT APP. 06-2020

180611-0300
ECT PROJECT NUMBER

AB MB
DESIGNED BY CHECKED BY

AB/ AK
DRAWN BY

CHECKED B


CHECKED B


APPROVED


STREAM PROFILE (2/2)

SCALE AS SHOWN












ROUGE RIVER
AOC HABITAT
PROJECT:
TAMARACK
CREEK - STREAM
AND WETLAND
RESTORATION
PROJECT

SOUTHFIELD, MICHIGAN



DETAILS (2/2)

SCALE AS SHOWN

